

THE FORRESTER GROUP  
INSIGHTFUL ENVIRONMENTAL SOLUTIONS™

**SOIL-GAS SITE INSPECTION REPORT**

Union Pacific Railroad  
Phoenix Rail Yard  
Phoenix, Arizona

Prepared for

**UNION PACIFIC RAILROAD**  
Environmental Management Group  
Omaha, Nebraska

Prepared by

**THE FORRESTER GROUP**  
5460 Ward Road, Suite 110  
Arvada, Colorado 80002  
[www.forrestergroup.com](http://www.forrestergroup.com)  
303-456-0400

November 9, 2004

## SOIL-GAS SITE INSPECTION REPORT

Union Pacific Railroad  
Phoenix Rail Yard  
Phoenix, Arizona

Prepared for

### UNION PACIFIC RAILROAD


Environmental Management Group  
Omaha, Nebraska

Prepared by

### THE FORRESTER GROUP

5460 Ward Road, Suite 110  
Arvada, Colorado 80002  
www.forrestergroup.com  
303-456-0400


November 9, 2004




Todd E. Manes  
Senior Associate



Dan W. Dowers  
Principal, Project Manager



Robert M. Kick, R.P.G., AZ #41245  
Principal



November 9, 2004

Project Number 15360000



## CONTENTS

<b>1</b>	<b>INTRODUCTION / BACKGROUND</b>	<b>1-1</b>
1.1	PURPOSE	1-1
1.2	INVESTIGATION PLANS	1-1
<b>2</b>	<b>SOIL-GAS INVESTIGATION</b>	<b>2-1</b>
2.1	DRILLING AND SAMPLING METHOD	2-1
2.2	CONSTITUENTS OF CONCERN	2-3
2.3	LABORATORY ANALYSES	2-3
2.4	DECONTAMINATION	2-4
2.5	INVESTIGATION DERIVED WASTES	2-4
2.6	QUALITY ASSURANCE / QUALITY CONTROL	2-4
2.6.1	Duplicate Samples	2-4
2.6.2	Field Equipment Blanks	2-5
2.6.3	Third-Party Field Oversight	2-5
2.6.4	Deviations From Work and Sampling Plan	2-5
<b>3</b>	<b>SOIL-GAS SAMPLING RESULTS</b>	<b>3-1</b>
3.1	FIELD SAMPLES	3-1
3.2	QUALITY ASSURANCE / QUALITY CONTROL SAMPLES	3-2
3.2.1	Duplicates	3-2
3.2.2	Background Sample	3-3
3.2.3	Field Equipment Blanks	3-3
3.2.4	Independent Data Review	3-3
<b>4</b>	<b>DISCUSSION OF RESULTS</b>	<b>4-1</b>
4.1	SOIL-GAS CONVERSION TO TOTAL SOIL CONCENTRATIONS	4-1
4.2	FORMER ROUNDHOUSE AREA	4-2
4.3	LOCOMOTIVE PARTS / DRUM STORAGE AREA – SOUTHEAST YARD AREA	4-2
<b>5</b>	<b>CONCLUSIONS AND RECOMMENDATIONS</b>	<b>5-1</b>
5.1	SIGNIFICANCE OF CHLORINATED HYDROCARBON IMPACT	5-1
5.2	IMPACTS IN THE FORMER ROUNDHOUSE AREA	5-1
5.3	IMPACTS IN THE LOCOMOTIVE PARTS / DRUM STORAGE AREA AND THE SOUTHEAST YARD AREA	5-1
5.4	RECOMMENDATIONS	5-2
<b>6</b>	<b>REFERENCES</b>	<b>6-1</b>

November 9, 2004

Project Number 15360000

---



THE FORRESTER GROUP  
INSIGHTFUL ENVIRONMENTAL SOLUTIONS™

APPENDIX A FIGURES  
APPENDIX B SITE PHOTOGRAPHS  
APPENDIX C TABLES  
APPENDIX D FIELD NOTES  
APPENDIX E LABORATORY REPORTS AND CHROMATOGRAMS  
APPENDIX F INDEPENDENT DATA VALIDATION REPORT





## **1 INTRODUCTION / BACKGROUND**

This investigation report details the sampling methods and sampling results from a soil-gas survey conducted between June 8, 2004 and June 29, 2004 at the former Southern Pacific Phoenix Rail Yard Site ("Site") in Phoenix, Arizona (Appendix A, Figure 1). The rail yard, located at 1301 East Harrison Street (Figure 2), is owned and operated by Union Pacific Railroad ("UPRR").

### **1.1 PURPOSE**

This investigation and assessment was performed voluntarily by UPRR under the oversight of the United States Environmental Protection Agency ("EPA") as part of its ongoing investigation in the area of Operable Unit 3 ("OU3") in the Motorola 52<sup>nd</sup> Street NPL site. The purpose of the soil-gas survey conducted on UPRR property was to determine if there was evidence of chlorinated hydrocarbon impact at the site. Additionally, if an impact was found, the soil-gas survey was to determine if a connection existed between the impact(s) found and the Motorola plume.

### **1.2 INVESTIGATION PLANS**

The "Final Site Inspection Work Plan" (Forrester 2004C) was finalized from the draft version (Forrester 2004A), based on written and verbal comments from EPA, Shaw Environmental ("Shaw" – consultant to EPA), and the Arizona Department of Environmental Quality ("ADEQ"). Field sampling methods are outlined in the "Final Field Sampling Plan" (Forrester 2004E). Quality assurance issues were outlined in the "Draft Quality Assurance Project Plan" (Forrester 2004D). Health and safety issues are outlined in the "Health and Safety Plan" (Forrester 2004B).



## 2 SOIL-GAS INVESTIGATION

Between June 8 and June 17, 2004, soil-gas samples were collected at 84 locations throughout the Site. All of these locations had been reviewed by EPA and Shaw during a site visit on April 27, 2004. An additional 19 locations were sampled between June 28 and June 29, 2004. Sample results are shown on Figure 3.

### 2.1 DRILLING AND SAMPLING METHOD

A direct-push rig provided by Johnson Environmental Technologies, using push rods with an approximate diameter of 1.5 inches, was used to collect all soil-gas samples (Appendix B, Photo 1). In many locations, very hard caliche, hard large cobbles, or concrete were encountered within three feet of the surface. In these cases, a solid drive tip was used first. If that failed, a pneumatic drill with a half-inch diameter, two-foot long drill concrete drill bit was used. If that failed, a 1.5-inch diameter concrete hole saw with 1.5-foot length shaft was attached to the pneumatic drill and used to drill a hole through the obstruction. If this failed, the hole was abandoned and another location was selected within a few feet of the first.

After breaking through the hard surface layer, the vapor probe tip was installed at the end of the push rods and pushed to the target depth of 10 feet below grade. Of the 103 sample locations, 89 of them were sampled at the 10-foot depth. The most shallow sample was at seven feet. To comply with a request by ADEQ to collect the sample from location SG-81 as deep as possible down to 15 feet, the sample from this location was taken at 12.5 feet, which was the depth of drilling refusal.

Once at total depth, the push rods were pulled up a few inches exposing the 3-inch long vapor probe tip to the subsurface (Appendix B, Photo 2). The tip was sealed off from the push rods by O-rings. At the surface, hydrated bentonite was placed around the exposed push rod in the annular space between the surface and the push rod to provide a surface seal (Photo 3). A cloth saturated with 1,1-difluorohexane (Staples® brand air duster) was placed over the bentonite seal to act as a leak check compound (Photo 4).

November 9, 2004

Project Number 15360000



Teflon™ tubing (quarter inch in diameter), that had been attached to the vapor probe prior to drilling, extended up the length of the push rods and emerged from the top of the rods approximately three feet.

For most of the locations, a relatively large volume of soil gas was purged (10 liters) to allow each location to have a large radius of influence. The large radius would help ensure that an area of significant impact of chlorinated hydrocarbons, that did not happen to be directly in contact with the vapor probe, would be detected. The following procedures were used to collect the soil-gas samples:

- The end of the tubing was attached to a series of valves which were connected to a flow meter and finally to an electric air pump (Photos 5 and 6). The sample stream was shielded with an umbrella so that sunlight did not directly contact the sample tubing, valves, or sample syringe during the purging or sampling processes. The pump was turned on and the flow meter was adjusted to 500 mL/minute.
- During the purging time of 10 minutes, the vacuum on the air pump was recorded periodically. In 101 of the 103 locations, the vacuum was zero indicating good vapor flow in the subsurface (an elevated vacuum would indicate poor air flow). At the same time vacuum readings were recorded, the vapor effluent on the air pump was tested with a photo ionization detector (PID). Since the PID was calibrated on a daily basis with isobutylene, the readings on the PID were not direct measurements of chlorinated hydrocarbon concentration in the soil-gas. However, they were used to help determine locations where to collect duplicate samples. Data collected during purging is presented on Table 1, Appendix C.
- After purging, the air pump was turned off. A new labeled plastic 60 mL syringe was attached to one of the valves. The valve was turned to allow soil gas to be drawn into the syringe. The syringe was filled at a rate of approximately 60 mL/minute. The valve was turned and this first 60 ml sample pushed out of the sample syringe into the atmosphere. The valve was turned again and another 60 mL sample of soil gas was drawn into the syringe. The entire closed valve assembly was removed from the tubing and left on the end of the syringe. The syringe was then placed in a small empty cooler to protect the

November 9, 2004

Project Number 15360000



THE FORRESTER GROUP  
INSIGHTFUL ENVIRONMENTAL SOLUTIONS™

sample from direct sunlight (Photo 7). The cooler with the syringe inside was then transported to the onsite mobile laboratory for analysis.

- In areas where chlorinated hydrocarbons were detected using the technique described above, additional sample locations were chosen in an attempt to more precisely determine the location of source areas. For this purpose, only enough purge volume was removed to purge the sample tubing. The tubing and vapor tip held approximately 70 mL of volume. The purge volume for these samples was set at 240 mL to ensure that the sample would be only soil-gas and not ambient air left in the sampling stream. For these samples, the air pump was not used. Instead, the sampling syringe was used to withdraw a sample from the sampling tube at a rate of 60 mL/minute. The syringe valve was adjusted and the collected gas was expelled into the PID tip for PID measurement. This process was repeated four times. On the fifth time, the collected sample was saved and put in the cooler for transport to the mobile laboratory.

Sample locations at which the smaller purge volume protocol was used are SG-63 through SG-66 and SG-82 through SG-103.

Appendix D contains the field notes recorded during the soil-gas survey.

After removing the push rods from each boring, the resulting hole was filled with bentonite chips to within a few inches of the surface, hydrated, and then sealed at the surface with either native soil or with asphalt as appropriate to match the surrounding area.

## 2.2 CONSTITUENTS OF CONCERN

The constituents of concern ("COCs") as dictated by EPA for this investigation were tetrachloroethylene ("PCE"), trichloroethylene ("TCE"), and the degradation products 1,1-dichloroethylene ("1,1-DCE"), cis-1,2-dichloroethylene ("cis-1,2-DCE"), trans-1,2-dichloroethylene ("trans-1,2-DCE"), and vinyl chloride ("VC").

## 2.3 LABORATORY ANALYSES

Soil-gas samples collected in plastic syringes were extracted within 30 minutes of collection by the onsite laboratory provided by H&P Laboratory and analyzed within 4 hours of extraction.

November 9, 2004

Project Number 15360000



THE FORRESTER GROUP  
INSIGHTFUL ENVIRONMENTAL SOLUTIONS™

These samples were analyzed using EPA Method 8260 modified for air analyses with sample results reported in  $\mu\text{g/L}$ . The detection limit for all analyses was 1  $\mu\text{g/L}$ .

## **2.4 DECONTAMINATION**

Before drilling at each location, the vapor sample housing, including the tip and the perforated steel tube through which the vapor sample was collected, was washed using the standard three-bucket wash technique with Alconox™ detergent and clean water. The washed pieces were then allowed to dry in the sun after cleaning.

After each sample, the Teflon® tubing was evacuated with purified air from a cylinder located on the drill rig. Periodically, the Teflon® tubing was changed when it became discolored or bent during drilling. New tubing was always used at the beginning of each day.

## **2.5 INVESTIGATION DERIVED WASTES**

Due to the direct-push drilling method employed, soil waste was not generated. The wash water used to decontaminate the sampling equipment was less than one gallon per day. At the end of the day, the water was placed into a 5-gallon bucket and allowed to evaporate (daytime temperatures were greater than 100 degrees F). Other wastes, including gloves, tubing, etc. were placed in trash bags and disposed of in the on-site trash receptacle.

## **2.6 QUALITY ASSURANCE / QUALITY CONTROL**

### **2.6.1 Duplicate Samples**

At an interval of approximately once every 10 samples, a duplicate syringe sample was collected. These samples were collected immediately after the original sample, having purged 60 mL of soil-gas between the original sample and the duplicate to clear any ambient air from the system. These duplicate samples were analyzed by the on-site mobile laboratory using EPA Method 8260. These samples are distinguished from the original samples by having the extension "8260D" added to the sample name.

For most locations where 8260 duplicates were collected, a second duplicate was also collected in steel laboratory-cleaned vacuum canisters. These samples were hand delivered on a daily basis to



Aerotech Environmental Laboratory in Phoenix, Arizona. Aerotech provided the clean canisters and the sample flow restriction connectors. The connectors allowed a sample flow rate of 0.5 liters/ minute. The sample vessels held approximately 2.7 liters and were allowed to fill for approximately 6 minutes to ensure that the vacuum in the canister would be zero (Photo 8).

These samples were analyzed using EPA Method TO-15. The TO-15 sampling and analysis method is both more accurate and more precise than the 8260 method. The detection limit for the TO-15 analyses varied with each sample. However, in general, the detection limit was between 0.003 and 0.1  $\mu\text{g/L}$ . The TO-15 duplicates were collected for comparison to the mobile laboratory results.

#### **2.6.2 Field Equipment Blanks**

Field Equipment blanks were collected at random intervals during the investigation. Blanks were always collected after decontaminating the sample apparatus but before changing the sample tubing to a new clean tube. Samples were typically collected after elevated PID readings were observed at a location or after a series of detections were reported by the laboratory. In general, field equipment blanks were not deemed necessary when COCs were not detected in samples after laboratory analysis. By definition, adverse soil-gas carryover could not have been occurring where laboratory analysis did not indicate concentrations above detection limits.


#### **2.6.3 Third-Party Field Oversight**

On behalf of EPA, field activities were overseen periodically by Mr. Ryan Pollyea of Shaw Environmental, Inc. Periodically during each day of the soil-gas survey, Mr. Pollyea would observe the drilling and sampling methods and was kept informed of progress and of any circumstances that arose that were out of the ordinary.

In addition, on June 15, 2004, Mr. Wayne Schiemann from the U.S. Army Corps of Engineers was at the Site for a number of hours observing the drilling and sampling.

#### **2.6.4 Deviations From Work and Sampling Plan**

The following lists situations in which the standard method of drilling and sampling was not followed or where other circumstances required modification of standard practices.



1. On June 9, a TO-15 duplicate sample was collected from location SG-8. This sample was collected immediately after the SG-FEB1 equipment blank spiked with 1,1-difluoroethane was collected. Based on information from Aerotech laboratory about this sample, it is likely that 1,1-difluoroethane carried over to the SG-8 sample. It was decided to not analyze this sample but to collect another TO-15 sample instead. Sample SG-10-10-TO15D was sampled in place of the aborted SG-8 sample.
2. During the analysis of the duplicate sample from location SG-26 on June 11, the laboratory experienced instrument failure. Upon restarting the instrument and using another aliquot of sample, the surrogate analyses were out of range. The third analysis of this sample was successful. However, because of the two previous analysis attempts, the sample volume available for the third analysis was less than the standard amount. Therefore, the detection limit for sample SG-26-10-8260D was increased from  $1\mu\text{g/L}$  to  $10\mu\text{g/L}$ .
3. On June 15, a number of samples (SG-44, SG-47, and SG-48) were reported by the laboratory to have low levels of the 1,1-difluoroethane in them. These levels were less than the reporting limit of  $10\mu\text{g/L}$ . The sample from location SG-51 was reported to have greater than  $10\mu\text{g/L}$  1,1-difluoroethane. Based on the sampling method, it was suspected that these leak-check detections did not represent a leak in the system, but were likely caused by an inadvertent contamination of the system with the compound. Up until that point, the 1,1-difluoroethane was being stored in a bag in the same box as the sampling syringes. After location SG-51, the 1,1-difluoroethane bag and the sampling syringes were put on opposite sides of the drill rig. A fresh box of syringes was used. From that point on, no other detections of the leak-check compound were reported.

To ensure that the original sample from SG-51 was not, in fact, caused by a leak in the sample stream, a second boring (SG-51R) was drilled and sampled at this location within two feet of the original. No COCs were detected in either SG-51 or SG-51R.

November 9, 2004

Project Number 15360000


---



THE FORRESTER GROUP  
INSIGHTFUL ENVIRONMENTAL SOLUTIONS™

4. On June 28, the mobile laboratory experienced temporary problems with the electrical generator. To make sure that the holding time would not be missed, the sample from location SG-91 was collected using a mini steel vacuum canister provided by H&P Laboratory. This canister was 350 mL in volume and took approximately two minutes to fill.
5. On June 29, the field work extended beyond the 12-hour window during which the mobile laboratory needed to run their initial and final calibration standards. Therefore, samples from location SG-102 and SG-103 were not collected in a syringe but were collected in the mini steel vacuum canisters provided by H&P Laboratory. These samples were driven back to Los Angeles, California in the mobile laboratory and were analyzed by H&P at their fixed-base facility in Los Angeles.
6. The chain-of-custody on which samples SG-72, SG-73, SG-74, SG-79, and SG-81 originally incorrectly listed the sample names and depths for these samples. The chain-of-custody was corrected and the database was updated to reflect this change.





### 3 SOIL-GAS SAMPLING RESULTS

Laboratory reports with chromatograms for all soil-gas sample analyses can be found in Appendix E. Appendix E also contains a CD-ROM on which all of the laboratory data has been stored electronically on Microsoft Excel® spreadsheets.

#### 3.1 FIELD SAMPLES

The results of the soil-gas analyses by the mobile laboratory are presented on Table 2 (Appendix C). Table 3 presents only those locations where concentrations of COCs above 1 µg/L were detected. These detections are also plotted on Figures 3 and 4.

Detectable concentrations of the COCs were found at only 22 of the 103 sample locations. PCE and trans-1,2-DCE were not detected above 1 µg/L at any of the locations. The highest concentration of any COC found was 7.5 µg/L of TCE at location SG-100.

There were no COC detections in any of the locations south of the portion of the yard currently used by Union Pacific (i.e. no detections in the automobile storage area, retention pond, truck wash, etc.). There were also no COC detections on the west end of the yard.

In only three areas of the yard where COCs were detected:

1. Former Roundhouse Area: Five locations had detectable VC only (Figure 3). All detections were below 2.5 µg/L. These detections do not indicate this area as a "source".
2. Locomotive Parts / Drum Storage Area: Ten locations had detectable concentrations of TCE, 1,1-DCE, cis-1,2-DCE, and VC (Figures 3 and 4). The first sample location to have had a detection in this area was SG-56. From there, 20-foot step-outs and then 40+ foot step-outs found the other locations, ending at the spur line, where similar chemical analyses exist. As with the roundhouse area, concentrations are very low (less than 7 µg/L) and do not indicate groundwater impact from surface activities at the rail yard.

November 9, 2004

Project Number 15360000



THE FORRESTER GROUP  
"INSIGHTFUL ENVIRONMENTAL SOLUTIONS"

3. Southeastern Yard Area: This area is south of the spur track noted above and north of the main track that makes up the southern portion of the working rail yard (Figures 3 and 4). Soil-gas samples in this area are distinct from those samples collected north of the spur line in that only TCE had detectable concentrations at seven locations. The highest TCE concentration in this area was 7.5  $\mu\text{g/L}$  from SG-100. Here again, this detection does not indicate this area as a "source".

### 3.2 QUALITY ASSURANCE / QUALITY CONTROL SAMPLES

#### 3.2.1 Duplicates

Comparison of the field samples, field sample duplicates, and fixed laboratory duplicates are shown on Table 4. There were 12 sets of duplicates, 10 of which included duplicates run at the fixed-base laboratory using Method TO-15. In general, the detection limit for the TO-15 method is 1000 times lower than for the 8260 method used by the mobile laboratory.

There were no sample pairs having a detection in the 8260 duplicate and no detection in the original. There was one sample (SG-64-10) in which there was a detection in the original while the 8260 duplicate reported no detection. All sample pairs between the original samples and the TO-15 duplicate agreed on nondetections at the field detection limit of 1.0  $\mu\text{g/L}$ .

There were only four sample pair locations with any COC at a detectable (greater than 1.0  $\mu\text{g/L}$ ) concentration: SG-64, SG-82, SG-89, and SG-94. Table 4 lists the relative percent difference ("RPD") between the original sample and the 8260 duplicate as well as the RPD between the original sample at the TO-15 duplicate for these sample pairs. Of the 15 comparisons (looking at all locations for all constituents), the RPD was greater than 30 percent for 9 of them.

As discussed on Page 6 of the independent sample validation report (Appendix F), when constituent detections are within five times the reporting limit (in this case, less than 5  $\mu\text{g/L}$  since the reporting limit was 1  $\mu\text{g/L}$ ), comparison of duplicates using RPD is not a valid method. In this case, duplicate precision is assessed by using a difference of four times the reporting limit as a guide. The differences between all of the 8260 duplicate pairs are within four times the reporting limit (4  $\mu\text{g/L}$ ).



There was only one sample result (TCE at SG-94) in which the TO-15 result was greater than the original sample. In none of the TO-15 sample pairs were any of the duplicate results greater than four times the reporting limit.

### **3.2.2 Background Sample**

Sample location SG-80, located near the west boundary of the yard, was chosen for background sample location based on the fact that no known railroad activities have taken place in this area since the time chlorinated hydrocarbons were available for general solvent use. As shown on Table 4, the 8260 original and duplicate samples did not have detectable concentrations of any of the COCs and the TO-15 sample had only low levels of TCE and PCE. Surprisingly, this location had the highest PCE detection ( $0.38 \mu\text{g/L}$ ) of any of the locations in which PCE was detected. We believe this demonstrates the ubiquity of chlorinated hydrocarbons in the subsurface throughout the metro Phoenix area.

### **3.2.3 Field Equipment Blanks**

Field equipment blank results are shown on Table 5. None of the COCs were detected in any of the field equipment blanks.

To confirm that the leak-check compound (1,1-difluorethane) could be detected by the method, the cloth being used to hold the leak-check compound was saturated and placed over the vapor tip during the collection of SG-FEB1. As shown on Table 5, the 1,1-difluorethane was detected in sample SG-FEB1 as reported by the mobile laboratory.

### **3.2.4 Independent Data Review**

Laboratory data from both the mobile laboratory and the fixed-base laboratory were validated by Diane Short & Associates, an independent data review company located in Lakewood, Colorado. The report from Diane Short & Associates can be found in Appendix F. Notwithstanding some documentation deviations on the chain-of-custody forms, the conclusion of the validation report is that "data are considered to be usable for project purposes ... . No qualifiers have been issued."



## 4 DISCUSSION OF RESULTS

### 4.1 SOIL-GAS CONVERSION TO TOTAL SOIL CONCENTRATIONS

In order to realistically assess the impact, if any, of the soil-gas data, the soil-gas results have been converted to soil concentrations using an equation presented in the CH2M Hill Technical Memorandum entitled "Proposed Application of the Groundwater Protection Level Model at the Honeywell 34<sup>th</sup> Street Facility." The memo is dated January 14, 2003 and was submitted to Kris Kommalan (Paschall) of the ADEQ.<sup>1/</sup>

Chemical properties of the COCs were taken from on-line sources. The highest concentration of each of the COCs found in the June soil-gas investigation was used as input to this equation ( $C_v$ ). Once total soil concentrations were obtained for each COC, these values were compared against Arizona Soil Remediation Levels as published in the Arizona Administrative Code (AAC), Title 18, Chapter 7, Article 2, Appendix A for both residential and industrial concentrations. The Arizona SRLs are Tier 1 soil cleanup levels deemed protective of human health and the environment.

A Microsoft Excel spreadsheet (Appendix C) was used to calculate  $C_T$ , the total soil concentration at the Site. Below are the results of this analysis.

---

<sup>1/</sup> We understand this equation has been used by the EPA and ADEQ to conduct plug-in evaluations at several subsites within the South Indian Bend Wash Superfund Site (CH2MHill 2003) and there is no reason for it to not be applicable here. The South Indian Bend Wash Superfund Site is located in the Phoenix metro area (the City of Tempe) not far from the Phoenix rail yard. Therefore, use of this equation for analysis of the soil-gas results from the Phoenix rail yard is appropriate because presumably it has already been accepted at other nearby sites by both EPA and ADEQ. The equation presented by CH2MHill is as follows:  $C_T = (((K_D)(P_b/K_H) + (\theta_w/K_H) + (\theta_T - \theta_w))(C_v))/P_b$ ; Where  $C_T$  = total soil concentration ( $\mu\text{g/kg}$ );  $C_v$  = total soil-gas concentrations ( $\mu\text{g/L}$ );  $K_D$  = soil-water partition distribution coefficient [ $K_{oc} * f_{oc}$ ] (L/kg);  $P_b$  = bulk density (kg/L);  $K_H$  = Henry's law constant (dimensionless);  $\theta_w$  = volumetric water content (dimensionless);  $\theta_T$  = total porosity (dimensionless);  $K_{oc}$  = organic carbon partition coefficient (L/kg);  $f_{oc}$  = fraction organic carbons (dimensionless)

November 9, 2004

Project Number 15360000



### TOTAL SOIL CALCULATION RESULTS

	TCE	1,1-DCE	CIS-1,2-DCE	VC
C <sub>T</sub> – (maximum calculated soil concentration at UPRR site.)	2,633	78	8,327	11
SRL - Residential	27,000	360	31,000	16
SRL - Industrial	70,000	800	100,000	35

a. All values in  $\mu\text{g}/\text{kg}$

As shown on the table above, the soil-gas COC concentrations detected at the Site do not represent soil concentrations that would require any additional remedial activity.

#### 4.2 FORMER ROUNDHOUSE AREA

Detections indicate historical release of chlorinated hydrocarbons in this area (i.e. detections are not caused by an upgradient source). Locations where detectable vinyl chloride occur are completely surrounded by other locations with non-detectable concentrations. There is also no distinct “source” location – as all soil gas concentrations were very low between 1.0 and 2.1  $\mu\text{g}/\text{L}$  detected from five locations spread out over approximately 25,000 square feet. The data show degradation to minimal levels of vinyl chloride only indicative that historical releases are highly unlikely to have impacted groundwater. It is our opinion that because there is no source location, any further soil sampling and/or assessment is unnecessary in this area.

#### 4.3 LOCOMOTIVE PARTS / DRUM STORAGE AREA – SOUTHEAST YARD AREA

These two areas, although somewhat distinct in chemical signature, need to be grouped together because their source is likely the same. That source is the known soil and groundwater impact of TCE located in the Adobe Air (Arvin) Facility located approximately 200 feet adjacent to and southeast of the rail yard. Information about the Arvin site relevant to the chlorinated hydrocarbon detections observed during the June 2004 soil-gas survey was obtained from the report, “Soil Contamination Source Removal and Groundwater Monitoring, North End of Warehouse Building, Adobe Air (Arvin) Facility, 500 South 15<sup>th</sup> Street, Phoenix, Arizona”

November 9, 2004

Project Number 15360000



THE FORRESTER GROUP  
INSIGHTFUL ENVIRONMENTAL SOLUTIONS™

prepared for Arvin by the environmental firm Scott, Allard & Bohannon, Inc on March 24, 1995 and submitted to ADEQ ("SAB" 1995). This report states the following:

- An initial investigation at the Arvin site conducted in 1989 found soil impacted with TCA, PCE, and 1,2-DCE.
- In 1991, six monitoring wells were installed around the Arvin site. Groundwater samples were collected from these wells quarterly for one year in 1992. Water levels from these wells indicated a general localized direction of groundwater flow from the Arvin site toward the UPRR rail yard.
- In 1994, soil impacted with chlorinated hydrocarbons was left in place following limited excavation in the warehouse area. Subsequent use of the VLEACH model by SAB indicated that residual TCE remaining in subsurface soil at the Arvin site would impact groundwater.
- Groundwater from well MW-4, located on the extreme northwest side of the facility, consistently had elevated concentrations of TCE, 1,1-DCE, 1,2-DCE, 1,1-DCA, and PCE. Of these constituents, TCE was the most abundant by approximately an order of magnitude over the other constituents.

A soil-gas survey conducted in 1993 at the Arvin site found TCE as the predominant contaminant with lesser concentrations of the degradation products.

In the 2004 soil-gas samples from the rail yard, all of the samples south of the spur track with detections had detections of TCE only. Since the TCE detections were near the detection limit, concentrations of other chlorinated hydrocarbons from the same source would be below the detection limit and not reported. Therefore, the chemical signature of the soil-gas is consistent with the chemical signature of the alleged source area. As shown on Figures 3 and 4 of SAB 1995, the location of the TCE-source area at the Arvin site in conjunction with groundwater flow directions indicated by the well monitoring data at the Arvin site clearly show that TCE-impacted groundwater from the Adobe facility has migrated to the UPRR rail yard. However, since SAB 1995, no further assessment of the offsite migration of chlorinated hydrocarbons from the Arvin site was ever undertaken.



The 2004 soil-gas detections of chlorinated hydrocarbons in the drum storage area can also be linked to Arvin. The appearance of degradation product in this area is easily explained and can be attributed to petroleum hydrocarbons that were also present. It is well known and reported in the technical literature that the presence of petroleum hydrocarbons greatly accelerates the degradation of chlorinated hydrocarbons because the biodegradation of chlorinated hydrocarbons is a secondary or co-metabolic process; the degradation of the petroleum being the primary process. In essence, the petroleum hydrocarbons acted a catalyst for degradation of the TCE.

Although they were not reported, H&P Laboratory made some qualitative assessments of petroleum hydrocarbons in locations SG-64, SG-88, SG-89 based on the chromatograms provided in Appendix F. These three locations are north of the spur track. This same information was also obtained from three locations south of the spur track: SG-85, SG-92, and SG-101. H&P reported that, based on the chromatograms from these locations, there was approximately an order of magnitude more petroleum hydrocarbons present in the locations north of the spur track than from the locations south of the spur track. All samples south of the spur track were reported to have petroleum hydrocarbon concentrations below the reporting limit.

The presence of petroleum hydrocarbons in the drum storage area coupled with localized groundwater flow provide a plausible argument that the chlorinated hydrocarbons north and south of the spur track originated from the same source but are being degraded at different rates due to varying chemical environments – the common source being the Adobe facility.

However, the soil-gas concentrations found in these areas are relatively low and the area of detected chlorinated hydrocarbons in the locomotive parts / drum storage area is bounded to the west, north, and east by areas where such constituents of concern have never been found. This indicates a confined impact only and thus that there is no chemical or hydrologic link between the chlorinated hydrocarbons in the locomotive parts / drum storage area and the wide-spread impacts associated with the Motorola plume.



## **5 CONCLUSIONS AND RECOMMENDATIONS**

### **5.1 SIGNIFICANCE OF CHLORINATED HYDROCARBON IMPACT**

- No "source" areas in soil could be identified anywhere at the Site. Low level concentrations of chlorinated hydrocarbons and degradation by-products detected over relatively large areas make it highly unlikely that were historical releases of any COCs impacting groundwater at the rail yard.
- Soil concentrations calculated from the data June 2004 soil-gas survey data are below Arizona Soil Remediation Levels for both residential and industrial site uses.
- Information gained from the historical record including recent sampling data and groundwater contours show that past activities at the Union Pacific rail yard cannot otherwise be contributing to chlorinated hydrocarbons in the Motorola plume.

### **5.2 IMPACTS IN THE FORMER ROUNDHOUSE AREA**

- No clear source location of vinyl chloride was established during the soil-gas survey.
- The area of VC detections is surrounded on all sides by locations where chlorinated hydrocarbons, including VC, were not detected. This indicates that groundwater impact and subsequent transport away from the source area did not likely occur.
- Vinyl chloride has not been detected in groundwater samples from OU3.

### **5.3 IMPACTS IN THE LOCOMOTIVE PARTS / DRUM STORAGE AREA AND THE SOUTHEAST YARD AREA**

- The low TCE detections and TCE plus degradation products detected in the locomotive parts storage area and southeast yard area most likely have their source at the Arvin Industries site. This site is located adjacent to the UPRR yard and has known chlorinated hydrocarbon impacts from previous documented use of chlorinated hydrocarbons.



November 9, 2004

Project Number 15360000



THE FORRESTER GROUP  
INSIGHTFUL ENVIRONMENTAL SOLUTIONS™

- Since only low levels of TCE and TCE-degradation products were found in this relatively large area of the UPRR yard, there is no indication that the original release site of these compounds is located on the UPRR yard.
- Geographic correlation of elevated concentrations of petroleum hydrocarbons at the UPRR site with the presence of TCE degradation products indicates that the source of chlorinated hydrocarbons in the southeast yard area and the locomotive parts / drum storage area are likely the same.
- With this area being completely surrounded by locations with non-detectable chlorinated hydrocarbon concentrations in soil-gas (except on the southeast side that abuts the Arvin site), there is no connection between the chlorinated hydrocarbon impacts detected in these areas and the Motorola plume.
- Soil-gas concentrations were relatively small and do not indicate the possibility of wide-scale impact nor impact to yard soil at a concentration even sufficient to require soil remediation.
- The Motorola plume is located north of the Site. The areas of the Site where chlorinated hydrocarbons were detected are all bounded to the north by locations where chlorinated hydrocarbons were not detected. Therefore, the impacts at the Site are chemically disconnected from the Motorola plume.

#### 5.4 RECOMMENDATIONS

- Any further investigation of Site soils would be unproductive without clearly identified, significant source areas. Therefore, further investigation of Site soils is unwarranted.
- Past releases of chlorinated hydrocarbons in the roundhouse area are not indicated beyond a minor or confined local impact. With neither a clear "source" area for these compounds nor concentrations reasonably indicative of groundwater impact, no further investigation or remedial effort in this area is needed.
- Chlorinated hydrocarbon impacts in the locomotive parts / drum storage area and the southeast yard area are locally. Offsite impacts are implicated from the adjacent Arvin

**Soil-Gas Site Inspection Report  
UPRR Phoenix Rail Yard**

**November 9, 2004**

**Project Number 15360000**

---



**THE FORRESTER GROUP**  
INSIGHTFUL ENVIRONMENTAL SOLUTIONS™

Industries site. Because these impacts appear to be minor and contained within these areas, no further investigation of these areas is warranted.

## 6 REFERENCES


- Arizona Department of Environmental Quality, May 5, 1995, Letter from Mr. Jeffrey P. Kulon, Project Manager, Remedial Projects Unit, ADEQ to Mr. Page E. Gifford, Counsel for Arvin Industries, regarding soil contamination source removal and groundwater monitoring report Arvin/Adobe Air facility, East Washington WQARF area.
- Arvin Industries, June 27, 1995, Letter from Mr. Page E. Gifford, Counsel for Arvin Industries, to Mr. Jeffrey P. Kulon, Project Manager, Remedial Projects Unit, ADEQ, regarding AdobeAir/ADEQ Soil & Groundwater Investigation.
- CH2MHill, January 14, 2003, "Proposed Application of the Groundwater Protection Level Model at the Honeywell 34<sup>th</sup> Street Facility", Technical Memorandum prepared by Darian Davies (CH2MHill) for Kris Kommalan (ADEQ).
- Scott, Allard,& Bohannon, Inc., January 25, 1993, "Groundwater Sampling, Fourth Quarter, 1992, Adobe Air (Arvin) Facility, 500 South 15<sup>th</sup> Street, Phoenix, Arizona."
- Scott, Allard,& Bohannon, Inc., March 24, 1995, "Soil contamination Source Removal and Groundwater Monitoring, North end of Warehouse Building, Adobe Air (Arvin) Facility, 500 South 15<sup>th</sup> Street, Phoenix, Arizona."
- The Forrester Group, Inc., February 11, 2004(A), "Draft Site Inspection Work Plan", Union Pacific Railroad, Phoenix Rail Yard, Phoenix, Arizona.
- The Forrester Group, Inc., March 26, 2004(B), "Health And Safety Plan", Union Pacific Railroad, Phoenix Rail Yard, Phoenix, Arizona.
- The Forrester Group, Inc., April 22, 2004(C), "Final Site Inspection Work Plan", Union Pacific Railroad, Phoenix Rail Yard, Phoenix, Arizona.
- The Forrester Group, Inc., May 17, 2004(D), "Draft Quality Assurance Project Plan", Union Pacific Railroad, Phoenix Rail Yard, Phoenix, Arizona.
- The Forrester Group, Inc., June 2, 2004(E), "Final Field Sampling Plan", Union Pacific Railroad, Phoenix Rail Yard, Phoenix, Arizona.

**APPENDIX A**  
**FIGURES**





M:\clients\FORRESTER\phoenix\12-03-Report\Phoenix zoom-nodata.dwg plotted: 11/16/2004



**LEGEND**

- SOIL-GAS SAMPLE LOCATION
- UNION PACIFIC RAILROAD PROPERTY

BY	DATE
DRAWN FR	7/14/04
CHECKED	
REVISED	
APPROVED	
APPROVED	



**THE FORRESTER GROUP**  
INSIGHTFUL ENVIRONMENTAL SOLUTIONS


**UNION PACIFIC RAILROAD-PHOENIX YARD**

**FIGURE 2**  
**SITE LAYOUT AND SOIL-GAS SAMPLE LOCATIONS MAP**  
JUNE 9-29, 2004

SCALE: 1"=400' DWG. NO.: Phoenix zoom-nodata.dwg



M:\clients\FORRESTER\phoenix\12-03-Report\Phoenix zoom.dwg plotted: 10/29/2004



# LEGEND

- MONITORING WELL LOCATION
- SAMPLE LOCATION WITH NO DETECTION
- SAMPLE LOCATION WITH VOC DETECTION
- (1.0) MOBILE LAB ANALYSIS RESULT FOR VINYL CHLORIDE IN (µg/L)

NOTE: DETECTION LIMIT FOR ALL VOCs IS 1 µg/L  
AT LOCATIONS WITH DETECTABLE VOC CONCENTRATIONS,  
VINYL CHLORIDE WAS THE ONLY VOC DETECTED EXCEPT IN  
LOCOMOTIVE PARTS STORAGE AREA (SEE FIGURE 4)

BY	DATE
DRAWN FR	12/3/03
CHECKED	
REVISED FR	7/1/04
APPROVED	
APPROVED	



THE FORRESTER GROUP  
INSIGHTFUL ENVIRONMENTAL SOLUTIONS

## UNION PACIFIC RAILROAD-PHOENIX YARD

FIGURE 3  
SOIL GAS SAMPLE RESULTS MAP

SCALE:


1"=400'

DWG. NO.:

Phoenix zoom.dwg



M:\clients\FORREST\phoenix\12-03-Report\Phoenix zoom.dwg plotted: 11/16/2004





**APPENDIX B**  
**SITE PHOTOGRAPHS**

Photographs From Soil-Gas Investigation  
Union Pacific Railroad, Phoenix Rail Yard  
Phoenix Arizona, June 2004

1



1  
Direct-push drill rig. Jackhammer pounds hollow pipe into ground to desired depth. Bottom of pipe is equipped with vapor-probe tip.

2



2  
Vapor probe tip exposed to show perforated pipe through which vapor sample is collected.



3



3  
The surface was sealed with hydrated bentonite clay to prevent sampling air from the surface.

4



4  
A towel saturated with 1,1-difluoroethane was placed over the bentonite seal to provide a method for checking for leaks from the surface.



5



5  
Teflon® tubing exiting the top of the push rod connected to sample syringe valves, filter, flow meter, then vapor purge pump (see Photo 6 below).

6



6  
Showing flow meter, vapor purge pump, and vacuum gauge. PID is yellow instrument resting on box on right.



7



7  
Sample syringe after sampling in cooler for delivery to on-site mobile laboratory.

8



8  
Duplicate sampling using steel canister.

**APPENDIX C**  
**TABLES**

Table 1  
Soil-Gas Purging Data  
UPRR Phoenix, Arizona  
June 2004

Date	Sample Location	PID (ppm)	Time (min:sec)	Vacuum (in)	Ambient (ppm)
6/9/2004	SG-1-9.5	0.0	0	0	0
6/9/2004	SG-2-10	4.5	1:30	0	0
		5.3	5:00	0	0
		6.2	7:15	0	0
		6.5	10:00	0	0
6/9/2004	SG-3-10	0.0	2:40	0	0
		0.0	10:00	0	0
6/9/2004	SG-4-10	0.8	2:22	0	0
		1.2	6:00	0	0
		1.1	2:36	0	0
6/9/2004	SG-5-10	1.0	2:30	0	0
		1.2	12:00	0	0
6/9/2004	SG-6-10	0.0	1:00	0	0
		0.0	6:00	0	0
		0.0	12:00	0	0
6/9/2004	SG-7-10	0.0	1:00	0	0
		0.0	10:00	0	0
6/9/2004	SG-8-10	2.5	4:00	0	0
		2.0	8:45	0	0
6/9/2004	SG-9-10	1.6	5:01	0	0
		1.8	8:30	0	0
		1.5	10:00	0	0
6/10/2004	SG-10-10	0.4	2:00	0	0
		0.4	10:00	0	0
6/10/2004	SG-11-10	1.6	1:00	0	0
		2.0	6:00	0	0
		1.6	10:00	0	0
6/10/2004	SG-12-10	11.0	2:40	0	0
		13.2	4:00	0	0
		15.2	0:00	0	0
6/10/2004	SG-13-10	12.5	2:45	0	0
		13.5	6:45	0	0
		13.5	0:00	0	0

Table 1  
Soil-Gas Purging Data  
UPRR Phoenix, Arizona  
June 2004

Date	Sample Location	PID (ppm)	Time (min:sec)	Vacuum (in)	Ambient (ppm)
6/10/2004	SG-14-10	10.8	2:00	0	0
		10.0	7:00	0	0
		3.0	0:00	0	0
6/10/2004	SG-15-10	11.2	2:00	0	0
		15.1	4:00	0	0
		18.1	0:00	0	0
6/10/2004	SG-16-10	13.8	2:15	0	0
		13.3	5:15	0	0
		13.2	0:00	0	0
6/10/2004	SG-17-10	5.7	3:00	0	0
		4.3	6:30	0	0
		4.7	0:00	0	0
6/10/2004	SG-18-9.5	8.5	1:00	0	0
		13.0	6:00	0	0
		13.4	11:00	0	0
6/10/2004	SG-19-10	10.2	2:00	0	0
		9.7	8:30	0	0
6/11/2004	SG-20-9	4.8	1:50	0	0
		5.2	5:00	0	0
		2.9	0:00	0	0
6/11/2004	SG-21-10	10.7	1:00	0	0
		11.4	0:00	0	0
6/11/2004	SG-22-9	5.5	1:45	0	0
		3.3	8:15	0	0
6/11/2004	SG-23-10	0.6	4:30	0	0.4
		0.6	7:00	0	0.4
		0.6	0:00	0	0.4
6/11/2004	SG-24-10	9.4	1:00	0	0.9
		15.3	7:03	0	0.9
		16.2	0:00	0	0.9
6/11/2004	SG-25-10	11.8	2:15	0	0
		12.7	8:30	0	0
		12.8	0:00	0	0



Table 1  
Soil-Gas Purging Data  
UPRR Phoenix, Arizona  
June 2004

Date	Sample Location	PID (ppm)	Time (min:sec)	Vacuum (in)	Ambient (ppm)
6/11/2004	SG-26-10	9.0	2:00	0	0.4
		10.7	7:00	0	0.4
		10.7	0:00	0	0.4
6/11/2004	SG-27-10	1.6	2:24	0	0.7
		0.1	8:30	0	0.7
		0.0	0:00	0	0.7
6/11/2004	SG-28-10	0.0	3:00	0	0.6
		0.0	6:15	0	0.6
		0.0	0:00	0	0.6
6/14/2004	SG-29-10	0.6	1:45	0	0
		0.0	0:00	0	0
6/14/2004	SG-30-10	3.9	4:00	0	0
6/14/2004	SG-31-10	8.9	1:30	0	0
		6.8	6:45	0	0
		3.2	0:00	0	0
6/14/2004	SG-32-10	4.3	1:00	0	0
		1.2	7:00	0	0
		1.0	0:00	0	0
6/14/2004	SG-33-10	1.3	1:30	0	0
		0.8	6:30	0	0
		0.2	0:00	0	0
6/14/2004	SG-34-10	0.7	1:00	0	0
		0.3	7:45	0	0
		0.2	0:00	0	0
6/14/2004	SG-35-10	0.9	1:00	0	0
		0.1	8:45	0	0
		0.1	0:00	0	0
6/14/2004	SG-36-10	0.5	1:00	0	0
		0.3	6:20	0	0
		0.3	0:00	0	0
6/14/2004	SG-37-10	1.5	1:00	0	0.1
		1.0	4:00	0	0.1
		0.5	0:00	0	0.1

Table 1  
Soil-Gas Purging Data  
UPRR Phoenix, Arizona  
June 2004

Date	Sample Location	PID (ppm)	Time (min:sec)	Vacuum (in)	Ambient (ppm)
6/14/2004	SG-38-10	0.7	1:30	0	0.4
		0.6	5:30	0	0.4
		0.3	0:00	0	0.4
6/14/2004	SG-39-10	0.6	2:45	0	0.2
		0.3	8:00	0	0.2
		0.2	0:00	0	0.2
6/14/2004	SG-40-10	0.6	6:15	0	0.2
		0.5	0:00	0	0.2
6/14/2004	SG-41-10	0.4	2:00	0	0.2
		0.5	6:30	0	0.2
		0.3	0:00	0	0.2
6/14/2004	SG-42-10	0.5	2:00	0	0.1
		0.5	6:30	0	0.1
		0.3	0:00	0	0.1
6/14/2004	SG-43-10	9.8	2:23	0	0.1
		13.7	8:00	0	0.1
		16.8	0:00	0	0.1
6/15/2004	SG-44-10	2.7	2:30	0	0.3
		1.6	8:00	0	0.3
		1.6	0:00	0	0.3
6/15/2004	SG-45-10	0.7	3:30	0	0
		0.7	7:45	0	0
		0.6	0:00	0	0
6/15/2004	SG-46-10	2.0	1:45	0	0.3
		1.0	6:00	0	0.3
		1.0	0:00	0	0.3
6/15/2004	SG-47-10	2.1	1:30	0	0.6
		1.6	6:30	0	0.6
		1.0	0:00	0	0.6
6/15/2004	SG-48-10	2.6	5:00	0	0.2
		2.4	7:15	0	0.2
		2.6	0:00	0	0.2
6/15/2004	SG-49-10	5.3	2:45	0	0
		2.1	7:00	0	0

Table 1  
Soil-Gas Purging Data  
UPRR Phoenix, Arizona  
June 2004

Date	Sample Location	PID (ppm)	Time (min:sec)	Vacuum (in)	Ambient (ppm)
6/15/2004	SG-50-10	2.5	1:45	0	0
		2.3	8:00	0	0
		2.6	0:00	0	0
6/15/2004	SG-51-10	1.2	2:30	0	0.1
		0.8	6:00	0	0.1
		0.9	0:00	0	0.1
6/15/2004	SG-52-10	0.3	1:00	0	0.1
		0.5	6:00	0	0.1
		0.4	0:00	0	0.1
6/15/2004	SG-53-10	1.6	2:30	3.5	0.2
		0.7	8:00	3.5	0.2
		0.8	0:00	3.5	0.2
6/15/2004	SG-54-10	12.5	2:00	0	0.2
		26.4	5:45	0	0.2
		23.1	0:00	0	0.2
6/15/2004	SG-55-10	36.2	2:45	0	0.3
		35.0	6:15	0	0.3
		38.2	0:00	0	0.3
6/15/2004	SG-51R-10	5.7	4:00	0	0.2
6/15/2004	SG-56-10	41.4	2:45	0	0.4
		47.2	7:30	0	0.4
		51.6	0:00	0	0.4
6/15/2004	SG-57-10	14.4	3:15	0.5	0.5
		7.6	7:00	0.5	0.5
		4.4	0:00	0.5	0.5
6/15/2004	SG-58-10	7.1	0:15	0	0.4
		4.5	6:00	0	0.4
		4.4	0:00	0	0.4
6/16/2004	SG-59-10	2.2	3:30	0	0.3
		1.5	8:10	0	0.3
		1.1	0:00	0	0.3
6/16/2004	SG-60-10	13.1	3:00	0	0
		16.1	8:15	0	0
		16.7	0:00	0	0

Table 1  
Soil-Gas Purging Data  
UPRR Phoenix, Arizona  
June 2004

Date	Sample Location	PID (ppm)	Time (min:sec)	Vacuum (in)	Ambient (ppm)
6/16/2004	SG-61-9	20.1	1:25	0	0.3
		12.2	6:00	0	0.3
		16.1	0:00	0	0.3
6/16/2004	SG-62-10	5.9	1:30	0	0.5
		6.3	6:45	0	0.5
		6.4	0:00	0	0.5
6/16/2004	SG-63-6	33.9	1:30	0	0
		42.2	2:36	0	0
		40.0	3:30	0	0
		40.4	5:00	0	0
6/16/2004	SG-64-10	11.0	1:00	0	0.4
		17.3	2:00	0	0.4
		18.7	3:00	0	0.4
		21.7	4:00	0	0.4
6/16/2004	SG-65-10	29.9	1:00	0	0.3
		73.1	2:00	0	0.3
		73.6	3:00	0	0.3
		74.0	4:00	0	0.3
6/16/2004	SG-66-10	122.0	1:00	0	0
		113.0	2:00	0	0
		112.0	3:00	0	0
		111.0	4:00	0	0
6/16/2004	SG-67-10	22.3	2:30	0	0.6
		36.5	6:45	0	0.6
		20.2	0:00	0	0.6
6/16/2004	SG-68-10	12.5	3:25	0	0.8
		9.2	7:15	0	0.8
		7.1	0:00	0	0.6
6/16/2004	SG-69-10	5.3	2:00	0	0.6
		2.3	7:30	0	0.6
		2.4	0:00	0	0.6
6/16/2004	SG-70-10	2.6	2:30	0	0.4
		2.6	8:00	0	0.4
		2.4	0:00	0	0.4

Table 1  
Soil-Gas Purging Data  
UPRR Phoenix, Arizona  
June 2004

Date	Sample Location	PID (ppm)	Time (min:sec)	Vacuum (in)	Ambient (ppm)
6/16/2004	SG-71-10	2.1	2:00	0	0.6
		1.6	7:00	0	0.6
		1.3	0:00	0	0.6
6/17/2004	SG-72-9	0.7	3:00	0	0.1
		0.3	7:15	0	0.1
		0.5	0:00	0	0.1
6/17/2004	SG-73-8.5	0.4	1:45	0	0
		0.1	7:00	0	0
		0.0	0:00	0	0
6/17/2004	SG-74-8.5	0.5	1:30	0	0
		0.1	0:00	0	0
6/17/2004	SG-75-10	1.0	2:00	0	0.2
		0.7	6:00	0	0.2
		0.4	0:00	0	0.2
6/17/2004	SG-76-10	1.4	2:15	0	0.1
		0.5	7:15	0	0.1
		0.4	0:00	0	0.1
6/17/2004	SG-77-10	1.0	1:30	0	0.2
		0.3	7:00	0	0.2
		0.2	0:00	0	0.2
6/17/2004	SG-78-10	0.4	2:45	0	0.2
		0.3	6:40	0	0.2
		0.1	0:00	0	0.2
6/17/2004	SG-79-9.5	0.2	1:00	0	0
		0.1	8:00	0	0
6/17/2004	SG-80-10	0.8	1:30	0	0.2
		0.7	5:00	0	0.2
		0.6	0:00	0	0.2
6/17/2004	SG-81-12.5	0.7	1:20	0	0.2
		0.2	7:00	0	0.2
		0.4	0:00	0	0.2
6/17/2004	SG-82-9	43.6	1:00	0	0.6
		63.8	2:00	0	0.6
		51.4	3:30	0	0.6
		59.5	4:20	0	0.6

Table 1  
Soil-Gas Purging Data  
UPRR Phoenix, Arizona  
June 2004

Date	Sample Location	PID (ppm)	Time (min:sec)	Vacuum (in)	Ambient (ppm)
6/17/2004	SG-83-10	40.8	1:00	0	0.6
		68.1	1:42	0	0.6
		60.7	2:45	0	0.6
		60.9	3:40	0	0.6
6/17/2004	SG-84-10	36.4	1:00	0	0.3
		65.4	1:44	0	0.3
		67.0	2:15	0	0.3
		67.0	3:00	0	0.3
6/28/2004	SG-85-10	0.0	0:30	0	0
		0.6	1:15	0	0
		0.0	2:00	0	0
		0.1	2:50	0	0
6/29/2004	SG-86-10	0.0	1:00	0	0
		12.1	2:00	0	0
		12.1	3:00	0	0
		16.5	4:00	0	0
6/29/2004	SG-87-10	4.6	1:00	0	0
		1.5	2:00	0	0
		0.0	3:15	0	0
		0.9	4:00	0	0
6/29/2004	SG-88-10	61.3	1:00	0	0
		80.8	1:50	0	0
		87.0	2:30	0	0
		85.1	3:30	0	0
6/29/2004	SG-89-10	56.7	1:00	0	0
		60.6	1:45	0	0
		59.6	1:45	0	0
		59.2	3:20	0	0
6/29/2004	SG-90-10	19.7	0:50	0	0
		22.8	1:30	0	0
		23.6	2:15	0	0
		22.1	3:20	0	0
6/29/2004	SG-91-10	0.7	0:50	0	0
		2.4	1:30	0	0
		3.6	2:45	0	0
		1.8	3:30	0	0

Table 1  
Soil-Gas Purging Data  
UPRR Phoenix, Arizona  
June 2004

Date	Sample Location	PID (ppm)	Time (min:sec)	Vacuum (in)	Ambient (ppm)
6/29/2004	SG-92-10	3.9	1:00	0	0
		4.9	2:00	0	0
		3.3	2:40	0	0
		2.3	3:30	0	0
6/29/2004	SG-93-10	0.0	0:45	0	0
		0.0	1:15	0	0
		0.0	2:45	0	0
		0.0	3:20	0	0
6/29/2004	SG-94-10	0.0	0:50	0	0
		0.6	1:30	0	0
		0.0	2:40	0	0
		1.3	3:30	0	0
6/29/2004	SG-95-10	1.8	0:05	0	0
		1.6	1:20	0	0
		0.3	2:10	0	0
		1.5	3:05	0	0
6/29/2004	SG-96-10	2.7	1:00	0	0
		38.7	2:00	0	0
		29.4	2:50	0	0
		14.7	3:50	0	0
6/29/2004	SG-97-10	0.0	0:05	0	0
		6.7	1:50	0	0
		7.6	2:50	0	0
		5.1	3:48	0	0
6/29/2004	SG-98-10	2.2	1:00	0	0
		5.0	2:00	0	0
		5.8	3:00	0	0
		4.6	3:50	0	0
6/29/2004	SG-99-10	0.0	0:45	0	0
		3.1	1:35	0	0
		2.7	2:40	0	0
		2.7	3:40	0	0
6/29/2004	SG-100-10	1.7	1:00	0	0
		4.4	1:50	0	0
		3.6	3:00	0	0
		3.1	3:50	0	0

Table 1  
Soil-Gas Purging Data  
UPRR Phoenix, Arizona  
June 2004

Date	Sample Location	PID (ppm)	Time (min:sec)	Vacuum (in)	Ambient (ppm)
6/29/2004	SG-101-10	3.8	0:50	0	0
		5.1	1:30	0	0
		3.4	2:30	0	0
		3.4	2:30	0	0
6/29/2004	SG-102-10	3.8	0:50	0	0
		5.1	1:30	0	0
		3.4	2:30	0	0
		3.4	3:20	0	0
6/29/2004	SG-103-10	3.0	1:00	0	0
		3.5	1:00	0	0
		3.0	3:00	0	0
		3.1	3:50	0	0



Table 2  
Soil-Gas Analytical Data Summary  
Mobile (Field) Lab  
UPRR Phoenix, Arizona  
June 2004

Sample Name	Date	Method	PCE	TCE	cis-1,2-DCE	trans-1,2-DCE	1,1-DCE	VC	1,1-Difluoroethane
			µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L
SG-1-9.5	6/9/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-2-10	6/9/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-3-10	6/9/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-4-10	6/9/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-5-10	6/9/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-6-10	6/9/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	1.7	< 10 U
SG-7-10	6/9/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-8-10	6/9/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-9-10	6/9/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-10-10	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-11-10	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-12-10	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-13-10	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-14-10	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-15-10	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-16-10	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-17-10	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-18-9.5	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-19-10	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-20-9	6/11/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-21-10	6/11/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	2.1 x 10 <sup>-3</sup>	< 10 U
SG-22-9	6/11/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-23-10	6/11/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-24-10	6/11/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	1.0	< 10 U
SG-25-10	6/11/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-26-10	6/11/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-27-10	6/11/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-28-10	6/11/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-29-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-30-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-31-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-32-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U

< # U = undetected at given value

Table 2  
Soil-Gas Analytical Data Summary  
Mobile (Field) Lab  
UPRR Phoenix, Arizona  
June 2004

Sample Name	Date	Method	PCE	TCE	cis-1,2-DCE	trans-1,2-DCE	1,1-DCE	VC	1,1-Difluoroethane
			µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L
SG-33-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-34-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-35-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-36-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-37-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-38-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-39-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-40-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-41-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-42-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-43-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-44-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-45-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-46-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-47-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-48-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-49-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-50-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-51R-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-52-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-53-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-54-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-55-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-56-10	6/15/2004	SW8260B	< 1 U	< 1 U	2.3 x 10 <sup>3</sup>	< 1 U	2.5	1.2	< 10 U
SG-57-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-58-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-59-10	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-60-10	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	2.1	< 10 U
SG-61-9	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	1.1	< 10 U
SG-62-10	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-63-10	6/16/2004	SW8260B	< 1 U	1.1	2.2	< 1 U	2.4	1.2	< 10 U
SG-64-10	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	1.1	< 1 U	< 10 U

< # U = undetected at given value

Table 2  
Soil-Gas Analytical Data Summary  
Mobile (Field) Lab  
UPRR Phoenix, Arizona  
June 2004

Sample Name	Date	Method	PCE	TCE	cis-1,2-DCE	trans-1,2-DCE	1,1-DCE	VC	1,1-Difluoroethane
			µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L
SG-65-10	6/16/2004	SW8260B	< 1 U	1.7	3.9	< 1 U	3.9	1.5	< 10 U
SG-66-10	6/16/2004	SW8260B	< 1 U	3.5	3.4	< 1 U	3.3	1.4	< 10 U
SG-67-10	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-68-10	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-69-10	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-70-10	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-71-10	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-72-9	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-73-8.5	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-74-8.5	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-75-10	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-76-10	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-77-10	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-78-10	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-79-9.5	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-80-10	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-81-12.5	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-82-10	6/17/2004	SW8260B	< 1 U	1.5	6.9	< 1 U	5.8	1.4	< 10 U
SG-83-10	6/17/2004	SW8260B	< 1 U	< 1 U	4.8	< 1 U	5.1	1.4	< 10 U
SG-84-10	6/17/2004	SW8260B	< 1 U	3.6	4.7	< 1 U	4.2	1.2	< 10 U
SG-85-10	6/28/2004	SW8260B	< 1 U	1.7	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-86-10	6/28/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-87-9	6/28/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-88-10	6/28/2004	SW8260B	< 1 U	3.5	2.9	< 1 U	2.5	1.1	< 10 U
SG-89-8.5	6/28/2004	SW8260B	< 1 U	1.6	3.2	< 1 U	3.8	1.1	< 10 U
SG-90-10	6/28/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-91-10	6/28/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-92-10	6/29/2004	SW8260B	< 1 U	3.9	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-93-10	6/29/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-94-10	6/29/2004	SW8260B	< 1 U	3.5	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-95-10	6/29/2004	SW8260B	< 1 U	3.3	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-96-10	6/29/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U

< # U = undetected at given value

Table 2  
Soil-Gas Analytical Data Summary  
Mobile (Field) Lab  
UPRR Phoenix, Arizona  
June 2004

Sample Name	Date	Method	PCE	TCE	cis-1,2-DCE	trans-1,2-DCE	1,1-DCE	VC	1,1-Difluoroethane
			$\mu\text{g/L}$	$\mu\text{g/L}$	$\mu\text{g/L}$	$\mu\text{g/L}$	$\mu\text{g/L}$	$\mu\text{g/L}$	$\mu\text{g/L}$
SG-97-10	6/29/2004	SW8260B	< 1 U	1.5	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-98-10	6/29/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-99-10	6/29/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-100-10	6/29/2004	SW8260B	< 1 U	7.5	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-101-10	6/29/2004	SW8260B	< 1 U	4.8	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-102-7	6/29/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-103-8	6/29/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U

**Table 3**  
**Soil-Gas Analytical Data Summary - Detections Only**  
**Mobile (Field) Lab**  
**UPRR Phoenix, Arizona**  
**June 2004**

Location ID	Sample Type	Sample Name	Date	Method	TCE	cis-1,2-DCE	1,1-DCE	VC
					µg/L	µg/L	µg/L	µg/L
SG-6-10	N	SG-6-10	6/9/2004	SW8260B				1.7
SG-21-10	N	SG-21-10	6/11/2004	SW8260B				2.1
SG-24-10	N	SG-24-10	6/11/2004	SW8260B				1.0
SG-56-10	N	SG-56-10	6/15/2004	SW8260B		2.3	2.5	1.2
SG-60-10	N	SG-60-10	6/16/2004	SW8260B				2.1
SG-61-9	N	SG-61-9	6/16/2004	SW8260B				1.1
SG-63-10	N	SG-63-10	6/16/2004	SW8260B	1.1	2.2	2.4	1.2
SG-64-10	N	SG-64-10	6/16/2004	SW8260B			1.1	
SG-65-10	N	SG-65-10	6/16/2004	SW8260B	1.7	3.9	3.9	1.5
SG-66-10	N	SG-66-10	6/16/2004	SW8260B	3.5	3.4	3.3	1.4
SG-82-9	N	SG-82-10	6/17/2004	SW8260B	1.5	6.9	5.8	1.4
SG-83-10	N	SG-83-10	6/17/2004	SW8260B		4.8	5.1	1.4
SG-84-10	N	SG-84-10	6/17/2004	SW8260B	3.6	4.7	4.2	1.2
SG-85-10	N	SG-85-10	6/28/2004	SW8260B	1.7			
SG-88-10	N	SG-88-10	6/28/2004	SW8260B	3.5	2.9	2.5	1.1
SG-89-8.5	N	SG-89-8.5	6/28/2004	SW8260B	1.6	3.2	3.8	1.1
SG-92-10	N	SG-92-10	6/29/2004	SW8260B	3.9			
SG-94-10	N	SG-94-10	6/29/2004	SW8260B	3.5			
SG-95-10	N	SG-95-10	6/29/2004	SW8260B	3.3			
SG-97-10	N	SG-97-10	6/29/2004	SW8260B	1.5			
SG-100-10	N	SG-100-10	6/29/2004	SW8260B	7.5			
SG-101-10	N	SG-101-10	6/29/2004	SW8260B	4.8			

Blank cells indicate compound was not detected.

**Table 4**  
**Soil-Gas Analytical Data Summary**  
**QA/QC Samples - Duplicate Analyses**  
**UPRR Phoenix, Arizona**  
**June 2004**

Location ID	Sample Type	Sample Name	Date	Method	PCE	TCE	cis-1,2-DCE	trans-1,2-DCE	1,1-DCE	VC	1,1-Difluoroethane
					µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L
SG-8-10	N	SG-8-10	6/9/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-8-10	FD	SG-8-10-8260D	6/9/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-10-10	N	SG-10-10	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-10-10	FD	SG-10-10-8260D	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-10-10	FD	SG-10-10-TO15D	6/10/2004	TO15	0.0050	< 0.0028 U	< 0.0020 U	< 0.0020 U	< 0.0020 U	< 0.0013 U	
SG-17-10	N	SG-17-10	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-17-10	FD	SG-17-10-8260D	6/10/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-17-10	FD	SG-17-10-TO15D	6/10/2004	TO15	< 0.069 U	< 0.055 U	< 0.040 U	< 0.040 U	< 0.040 U	< 0.026 U	
SG-26-10	N	SG-26-10	6/11/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-26-10	FD	SG-26-10-8260D	6/11/2004	SW8260B	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U
SG-26-10	FD	SG-26-10-TO15D	6/11/2004	TO15	0.10	0.19	0.17	< 0.040 U	< 0.040 U	0.91	
SG-30-10	N	SG-30-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-30-10	FD	SG-30-10-8260D	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-30-10	FD	SG-30-10-TO15D	6/14/2004	TO15	< 0.14 U	< 0.11 U	< 0.080 U	< 0.080 U	< 0.081 U	0.24	
SG-42-10	N	SG-42-10	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-42-10	FD	SG-42-10-8260D	6/14/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-42-10	FD	SG-42-10-TO15D	6/14/2004	TO15	< 0.0034 U	< 0.0028 U	< 0.0020 U	< 0.0020 U	< 0.0020 U	< 0.0013 U	
SG-54-10	N	SG-54-10	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-54-10	FD	SG-54-10-8260D	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-54-10	FD	SG-54-10-TO15D	6/15/2004	TO15	< 0.069 U	< 0.055 U	< 0.040 U	< 0.040 U	< 0.040 U	< 0.026 U	
SG-64-10	N	SG-64-10	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	1.1	< 1 U	< 10 U
SG-64-10	FD	SG-64-10-8260D	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-64-10	FD	SG-64-10-TO15D	6/16/2004	TO15	< 0.14 U	0.12	0.72	< 0.080 U	1.1	0.52	

RPD

0.0

< # U = undetected at given value  
8260B samples were analyzed with mobile lab  
TO15 samples were analyzed at fixed lab

**Table 4**  
**Soil-Gas Analytical Data Summary**  
**QA/QC Samples - Duplicate Analyses**  
**UPRR Phoenix, Arizona**  
**June 2004**

Location ID	Sample Type	Sample Name	Date	Method	PCE	TCE	cis-1,2-DCE	trans-1,2-DCE	1,1-DCE	VC	1,1-Difluoroethane
					µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L
SG-78-10	N	SG-78-10	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-78-10	FD	SG-78-10-8260D	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-78-10	FD	SG-78-10-TO15D	6/17/2004	TO15	0.012	< 0.0055 U	< 0.0040 U	< 0.0040 U	< 0.0040 U	< 0.0026 U	
SG-80-10	N	SG-80-10	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-80-10	FD	SG-80-10-8260D	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-80-10	FD	SG-80-10-TO15D	6/17/2004	TO15	0.38	0.013	< 0.0040 U	< 0.0040 U	< 0.0040 U	< 0.0026 U	
SG-82-9	N	SG-82-10	6/17/2004	SW8260B	< 1 U	1.5	6.9	< 1 U	5.8	1.4	< 10 U
SG-82-9	FD	SG-82-9-TO15D	6/17/2004	TO15	< 0.14 U	0.72	3.8	< 0.080 U	2.8	0.57	
RPD						70.3	57.9		69.8	84.3	
SG-89-8.5	N	SG-89-8.5	6/28/2004	SW8260B	< 1 U	1.6	3.2	< 1 U	3.8	1.1	< 10 U
SG-89-8.5	FD	SG-89-8.5-8260D	6/28/2004	SW8260B	< 1 U	1.3	2.7	< 1 U	3.4	1.0	< 10 U
SG-89-8.5	FD	SG-89-8.5-TO15D	6/28/2004	TO15	0.076	0.94	1.8	< 0.040 U	1.9	0.49	
RPD						20.7	16.9		11.1	9.5	
RPD						74.0	72.0		66.7	61.6	
SG-94-10	N	SG-94-10	6/29/2004	SW8260B	< 1 U	3.5	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-94-10	FD	SG-94-10-8260D	6/29/2004	SW8260B	< 1 U	2.9	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
SG-94-10	FD	SG-94-10-TO15D	6/29/2004	TO15	0.16	5.3	< 0.040 U	< 0.040 U	0.052	< 0.026 U	
RPD						18.8					
RPD						120.5					

< # U = undetected at given value  
8260B samples were analyzed with mobile lab  
TO15 samples were analyzed at fixed lab

**Table 5**  
**Soil Gas Analytical Data Summary**  
**QA/QC Samples - Field Equipment Blanks**  
**UPRR Phoenix, Arizona**  
**June 2004**

Location ID	Sample Type	Sample Name	Date	Method	PCE	TCE	cis-1,2-DCE	trans-1,2-DCE	1,1-DCE	VC	1,1-Difluoroethane
					µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L
FieldQC	EB	SG-FEB1	6/9/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	74
FieldQC	EB	SG-FEB2	6/15/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
FieldQC	EB	SG-FEB3	6/16/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
FieldQC	EB	SG-FEB4	6/17/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U
FieldQC	EB	SG-FEB5	6/28/2004	SW8260B	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 1 U	< 10 U

< # U = undetected at given value



**Soil Concentration Calculations  
From Soil-Gas Sampling Results  
UPRR Phoenix, Arizona  
June 2004**

Variable	Definition	Units	Value
$C_t$	total soil concentration	$\mu\text{g/kg}$	
$C_v$	total soil-vapor concentraion	$\mu\text{g/L}$	
$K_d$	soil-water partioning distribution coefficient ( $K_{oc}$ )( $f_{oc}$ )	$\text{L/kg}$	
$P_b$	bulk density	$\text{kg/L}$	1.7
$K_H$	Henry's Law constant	$\text{atm}\cdot\text{m}^3 / \text{mol}$	
$K'_H$	Henry's Law constant ( $K_H / RT$ )	dimensionless	
$\theta_w$	volumetric water content	dimensionless	0.045
$\theta_T$	total porosity	dimensionless	0.5
$K_{oc}$	organic carbon partition coefficient	$\text{L/kg}$	
$f_{oc}$	fraction organic carbon	dimensionless	0.0012
$R$	gas constant	$\text{L}\cdot\text{atm}/\text{K}\cdot\text{mol}$	0.082057
$T$	temperature (20 °C)	Kelvin	293.15

Variable	TCE	1,1-DCE	cis-1,2-DCE	VC
$K_H$	0.020	0.19	0.0017	0.695
$K'_H$	0.000831	0.007899	0.0000707	0.028892
$K_{oc}$	221	65	49	98
$K_d$	0.2652	0.078	0.0588	0.1176

	TCE	1,1-DCE	cis-1,2-DCE	VC	
$C_v$	7.5	5.8	6.9	2.1	highest concentrations from June 2004 investigation

	TCE	1,1-DCE	cis-1,2-DCE	VC	
$C_T$ ( $\mu\text{g/kg}$ )	2633	78	8327	11	This is where the calculation is made

<b>Arizona Soil Remediation Levels</b>		<b>Residential</b>	27000	360	31000	16	$\mu\text{g/kg}$
		<b>Industrial</b>	70000	800	100000	35	$\mu\text{g/kg}$

SRLs from Arizona Administrative Code, Title 18, Chapter 7, Article 2, Appendix A (non-residential)

**APPENDIX D**  
**FIELD NOTES**

Phoenix

6/8/04

6:00 Arrive on site

Lab here (RUSS) DAN DOWERS,  
SCOTT JOHNSON (rig)

6:45 Safety Briefing

6:50 Problems with LAB.

7:00 WAYNE (ACE) Arrives

7:15 RYAN PAULSEN (Shaw) Arrives 602-677-  
9474

7:40 WAYNE LEAVES

10:30 Lab can't be fixed today  
will send out part and  
new lab everyone leaves  
site.

TODD MANES

UPR

Wed

6/9/04 Phoenix

Zoff E. Mauer

6:00 Arrive on site

Scotty Darr Russ, Josh (new lab)

New lab on site

6:15 Safety briefing

6:25 Move to SG-1

7:00 Weekly check system less

three 1/2" vacuum lines in line  
c 17"

7:28 Began SG-1

38° 56.218 N 33° 26.551 N

94° 45.668 W 112° 03.175 W

7:50 BWH SG-1-9.5 gas console  
2' 26" cable layer

7:57 Began SG-1 Purge 0 vacuum

8:02 PID 0.0

8:08 SG-1-9.5 @ 8:08 Sampled

taken to lab PID 0.0

Purge 10 minutes @ 500 m/min

Wed

UPR

Zoff E. Mauer 6/9/04 Phoenix

8:23 Began drilling SG-2

8:35 hole cased in wood E 1 ft  
start again.

8:58 Start purge SG-2-10

PID 4.5 ppm @ 1:30 min

0" vacuum

38° 56.218 N 33° 26.550 N

94° 45.668 W 112° 03.173 W

6:2 ppm @ 5:00 purge

6:2 ppm @ 7:15

9:08 Sampled SG-2-10 @ 9:08

Gas ppm @ 10:00

9:23 Began SG-3

9:40 Began Purge

0" vacuum

0.0 ppm @ 2:40

38° 56.218 N 33° 26.550 N

94° 45.668 W 112° 03.212 W

9:50 Sampled SG-3-10

0.00 ppm

~~Wed~~ Wed

6/9/04 OPR Phoenix Add Phoenix

10:00 Begin Drilling SG-4

10:26 begin purge SG-4-10

0" Vacuum  
33° 26.543 N

112° 03.236 W

0.8 ppm c 2.22

1.2 ppm c 6:00

10:40 Sample SG-4-10

1.1 ppm

End of vapor tube black with  
subsurface substance. Changing  
tubing

11:00 SG-5 Begin drilling

11:17 Auger refused c 6' SG-5  
moved 14' NE

11:24 SG-5 begin again

11:38 began SG-5 purge  
1.0 ppm c 2:30

~~Wed~~ Wed

Add E Phoenix UPR Phoenix 6/9/04

83° 26.546 N

112° 03.246 W

11:50 Sample SG-5-10

1.2 ppm

12:05 begin SG-6

12:23 begin SG-6-10 Purge

0.0 c 1:00 0" vacuum

33° 26.645 N

112° 03.246 W

0.0 c 6:00

12:35 Sample SG-6-10

0.0 ppm

12:45 begin drill SG-7 33° 26.552 N

112° 03.235 W

13:00 begin purge SG-7-10

0.0 c 1:00 0" vacuum  
ppm

13:10 Sample SG-7-10

0.0 c 10:00  
ppm

Wed

6/9/04 UPR Phoenix

13:35 ~~B SG-7-10~~

SG-FE61

Winged Leach checked way around pole tip

WINDY

13:40 Begin Drill SG-8

13:52 Begin purge SG-8-10

2.5 ppm @ 4:00 0" vacuum

33° 26.533N

112° 03.285W

2.0 ppm @ 8:45

14:05 Sample SG-8-10

14:06 SG-8-10-82600

14:15 SG-8-10-7015D

14:32 Begin SG-9

14:48 Begin Purge SG-9-10

16 ppm @ 5:01 0" Vacuum

33° 26.532N

112° 03.295W

1.5 ppm @ 8:30

Wed

UPR Phoenix 6-19/04

14:59 Sample SG-9-10

1.5 ppm

Pre-drilled SG-10, 11 to 3'

10:45 Left site

DAN DIVERS took 7015  
sample to Norvatech

David E. Thomas



Thurs

6/10/04 VPR Phoenix Josh E. James

5:00 Arrive on site

5:15 Safety meeting

dilling setup

6:18 Begin SG-10

6:25 Begin purge SG-10-10

0" vacuum

33° 26.548 N

112° 03.305 W

6:36 Sample SG-10-10

0.1 ppm (bars) @ 2:00

0.4 ppm @ 10:00

6:37 Take SG-10-10-8260 D

6:38 Take SG-10-10-7015 D

6:59 Begin dilling SG-11

7:10 Begin purge SG-11-10

0" vacuum

1.6 ppm @ 1:00

33° 26.546 N

112° 03.290 W

2.0 @ 6:00  
ppm

Thurs

Josh E. James - VPR Phoenix 6/10/04

7:20 Sampled SG-10-10

1.6 ppm

7:36 begin dilling SG-12

8:00 begin purge SG-12-10

0" vac

33° 26.547 N

112° 03.277 W

11 ppm @ 2:40 13.2 ppm @ 4:00

8:10 Sampled SG-12-10

15.2 ppm

8:20 begin dilling SG-13

8:37 Begin Purge SG-13-10

0" vac 12.5 ppm @ 2:45

33° 26.548 N

112° 03.268 W

17.5 ppm @ 6:45

Thurs

6/10/04 UPRC Channel Paul E. Bremer  
8:47 SG-13-10 sampled

13.5 ppm

9:05 begin drilling SG-14  
hit concrete @ 2.5'  
moving 2' East

9:10 Restart SG-14

9:29 begin large SG-14-10

0" vac  
11.8 ppm @ 2:00  
33° 26' 56.3 N  
112° 03' 26.8 W  
10.0 ppm @ 2:00

9:39 Sampled SG-14-10  
3.0 ppm

9:58 begin drill SG-15  
concrete @ 1'  
using concrete crew

Thurs

Paul E. Bremer = UPRC Channel 6/10/04  
10:33 begin large SG-15-10

0" vac 11.2 ppm @ 2:00  
33° 26' 56.5 N  
112° 03' 29.7 W  
15.1 ppm @ 4:00

10:43 Sample SG-15-10  
18.1 ppm

10:57 begin drill SG-16  
concrete  
bent rod @ 5'  
moving 7' East  
2' South

12:21 begin large SG-16-10  
33° 26' 56.2 N  
112° 03' 29.6 W  
0" vac 13.8 ppm @ 2:15  
13.3 ppm @ 5:15

12:31 Sample SG-16-10  
13.2 ppm



Thompson

6/10/24 UPRC Phoenix Judd & Howard

1325 Began drill SG-17  
1335 Began purge SG-17-10  
0" VAC 5.7 ppm @ 3:00

4.3 ppm @ 6:30  
33° 26.558N  
112° 03.313W

1345 Sampled SG-17-10  
4.7 ppm

~~1346 Sampled SG-17-10 - 82.600~~

1347 Sampled SG-17-10 - 107.540  
1354 Sampled SG-17-10 - 82.600

1500 Began drilling SG-18

1503 Began purging SG-18-9.5  
8.5 ppm @ 1:00  
0" VAC

33° 26.573N  
112° 03.294W  
130 @ 6:00

Thompson

UPRC Phoenix 6/10/24

15144 Sampled SG-18-9.5  
13.4 ppm

1550 Began SG-19 drilling

1610 Began purging SG-19-10  
0" VAC 10.2 @ 2:00  
33° 26.575N  
112° 03.310W  
9.7 ppm @ 8:30

1620 Sampled SG-19-10

1700 Leave site  
RUS took TO15 sample to  
Aero Tech  
Judd & Howard

6/19/04

UPRR Phoenix

Josh E. Hansen

5:00 Arrive on site

5:30 Safety meeting

6:15 begin drilling SG-20  
 auger ahead @ 2' mark w 3'

hit concrete again  
 moved 5' E and 10' S  
 hit concrete again  
 going back to original spot  
 and using drill

7:43 begin Purse SG-20-9  
 0" vac  
 4.8 ppm @ 1:50  
 33° 26.572N  
 112° 03.280W  
 5.2 ppm @ 5:00  
 7:53 Sampled SG-20-9  
 2.9 ppm

6/19/04

UPRR Phoenix

Josh E. Hansen

8:10 begin SG-21 drilling

8:43 begin Purse SG-21-10  
 0" vac 33° 26.575N  
 10.7 ppm 1:00 112° 03.269W

8:53 Sample SG-21-10  
 11.4 ppm

9:14 begin drilling ~~SG-22-10~~

9:34 begin Purse SG-22-9  
 0" vac 5.5 ppm @ 1:45  
 33° 26.521N  
 112° 03.258W  
 3.3 ppm @ 8:57

9:44 Sampled SG-22-9

9:55 begin SG-23  
 2 holes - referred @ 157  
 216 on top of stone SG-2315  
 on map

Fr 14

10:19 VPR Phoenix  
Start 3<sup>rd</sup> at night @ SG-23

4th attempt w/d drill

11:02 Begin purge SG-23-10

0" vac 33° 26, 52.8 N

112° 03, 24.9 W

0.6 ppm @ 4:30 ambient is

0.6 ppm @ 7:00 0.4 ppm

11:12 Sampled SG-23-10

0.4 ppm

11:38 Begin drilling SG-24

moved to 4' west because of buried electrical lines

11:47 Begin purging SG-24-10

0" vac 33° 26, 52.7 N

112° 03, 27.3 W

9.4 ppm @ 1:00 0.9 ppm ambient

15.3 ppm @ 7:30

Fr 14

11:57 VPR Phoenix  
Sampled SG-24-10

16.2 ppm

12:10 Begin drilling SG-25

hit concrete

cored to 18"

Conch break

13:30 Begin purge SG-25-10

0" vac 33° 26, 59.5 N

112° 03, 29.2 W

11.8 ppm @ 2:15

12.7 ppm @ 8:30

13:40 Sampled SG-25-10

12.8 ppm

13:58 Begin drilling SG-26

14:06 Begin purging SG-26-10

0" vac 33° 26, 59.2 N 0.4 ppm

112° 03, 29.7 W

9.8 @ 2:00

16.7 @ 7:00

14:16 Sampled

Time

6/14/04 VPRC Phoenix Road E. Howe

14:16 Sampled SG-26-10  
10.7 ppm

14:17 Sampled SG-26-10-82100 D

14:18 Sampled SG-26-10-TR15 D

14:45 begin drilling SG-27

used concrete core - Computed

15:15 Begin Logging SG-27

0" vac 1.6 ppm @ 2.24 0.7 ppm @

33° 26.693 N

112° 03.307 W

0.1 ppm @ 8:30

15:25 Sampled SG-27-10

0.0 ppm

15:40 begin SG-28 drilling

15:48 Begin Logging SG-28-10

0" vac 0.0 ppm @ 3:00 Amb 0.6

33° 26.602 N

112° 03.307 W

0.0 ppm @ 6:15

Time

VPRC Phoenix 6/14/04

15:58 Sampled SG-28-10

0.0 ppm

16:38 Left Site - take 70-5 Sample to

Field E. Howe - marked



MON

6/14/04 UPRC Phoenix Zolt E. James

5:00 Arrived on site, calibrate R/R  
6:00 Begin Drilling SG-29  
6:12 Begin Purge SG-29-10  
0" Vac 0.6 ppm @ 1:45 0.0 ambient  
33° 26.600N  
112° 03.295W

6:22 Sampled SG-29-10  
0.0 ppm

6:45 Begin Drilling SG-30-10  
6:50 Begin Purge SG-30-10  
0" Vac 3.9 ppm @ 4:00 0.0 ambient  
33° 26.604N  
112° 03.273W

7:00 Sampled SG-30-10

7:01 Sampled SG-30-10-8260D

7:03 Sampled SG-30-10-J565D

MON

6/14/04 UPRC Phoenix Zolt E. James

7:30 Begin Drilling SG-31  
7:36 Begin Purge SG-31-10  
0" Vac 8.9 ppm @ 1:30 0.0 ambient  
33° 26.650N  
112° 03.229W  
0.8 ppm @ 6:45

7:46 Sampled SG-31-10  
3.2 ppm

8:07 Begin Drilling SG-32-10 (near Switchman's  
shanty @ 16<sup>th</sup> st)

8:18 Begin Purge SG-32-10  
0" Vac 4.3 ppm @ 1:00  
33° 26.637N  
112° 02.924W

8:28 Sampled SG-32-10  
1.0 ppm @

8:52 Begin Drilling SG-33

Mon

6/14/04 UPRR Phoenix

9:06 Begin Purge SG-33-10

0" vac 1.3 ppm @ 1:30 0.0 amb

33° 26.60N 112° 03.49W 0.8 ppm @ 6:30

9:16 Sampled SG-33-10

0.2 ppm

9:27 Begin drilling SG-34

9:37 Begin Purge SG-34-10

0" vac 0.7 ppm @ 1:00 0.0 ppm amb

33° 26.590N

112° 03.490W

0.3 ppm @ 7:45

9:47 Sampled SG-34-10

0.2 ppm

10:02 Begin drilling SG-35

10:08 Begin Purge of SG-35-10

0" vac 0.9 ppm @ 1:00

33° 26.584N

112° 03.490W 0.1 ppm @ 8:45

10:18 Sampled SG-35-10

0.1 ppm

0.0 Amb

Mon

6/14/04 UPRR Phoenix

10:34 Begin drilling SG-36

10:45 Begin Purge SG-36-10

0" vac 0.5 ppm @ 1:00 0.0 amb

33° 26.590N

112° 03.500W

0.3 ppm @ 6:30

10:55 Sampled SG-36-10

0.3 ppm

11:05 Met with Jerry of UPRR to locate bridge

North of tracks by grad office plus bridge with D/C

11:20 Begin drilling SG-37

concrete at surface moved SW 3'

auger refused @ 7.5'

moved

11:50 Begin Drilling SG-37-10

12:00 Begin Purge SG-37-10

0" VAC 1.5 ppm @ 1:00 min 0.1 amb

1.0 ppm @ 4:00

33° 26.587N

112° 03.510W

12:40 Sampled SG-37-10

0.5 ppm

MON

North E. Phoenix

6/14/64 USAR Phoenix  
Begin drilling SG-38

13:10 Begin Purg SG-38-10

0" vac 0.7 ppm @ 1130 0.14 ppm Amb

33° 26.573N

112° 03.510W

0.6 ppm @ 5:30

13:20 Sampled SG-38-10

0.3 ppm

13:30 Begin drilling SG-39

13:43 Begin Purg SG-39-10

0" vac 0.1 ppm @ 2:45 0.12 ppm Amb

33° 26.590N

112° 03.510W

0.9 ppm @ 8:00

13:53 Sampled SG-39-10

0.2 ppm

14:04 Begin drilling SG-40

MON

North E. Phoenix

6/14/64

14:15 Begin Purg SG-40-10

0" vac

33° 26.602N

112° 03.530W

0.6 ppm @ 6:15

14:25 Sampled SG-40-10

0.5 ppm

14:49 begin drilling SG-41

14:58 Begin purg SG-41-10

0" vac 0.4 ppm @ 2:00 0.2 amb

33° 26.596N

112° 03.564W

1.6 ppm

15:08 Sampled SG-41-10

0.3 ppm

15:16 Begin drilling SG-42

15:28 Begin Purg SG-42-10

0" vac 0.5 ppm @ 2:00

33° 26.588N

112° 03.569W

0.5 ppm @ 6:30

0.1 amb

MON

6/14/04 WPCR Phoenix

15:38 Sampled SG-42-10

0.3 ppm

15:39 Sampled SG-42-6-82600

15:41 Sampled SG-42-10-701510

15:57 Begin drilling SG-43

0" UAC 9.8 ppm @ 2.23 0.1 ppm Amc

33° 20.595 N

112° 03.577 W

13.7 ppm @ 8:00

16:07 Sampled SG-43-10

16.8 ppm

16:45 Leave site for AeroTech

John E. Travers

TUES

John E. Travers WPCR Phoenix 6/15/04

5:00 Arrived

5:30 Safety meeting

5:59 Begin drilling SG-44

6:07 Begin drilling SG-44-10

0" UAC 2.7 ppm @ 2:30 0.3 ppm

33° 20.69 N

112° 03.596 W

10.6 ppm @ 8:00

6:17 Sampled SG-44-10

11.6 ppm @

6:32 Begin drilling SG-45

6:43 Begin drilling SG-45-10

0" UAC 0.7 ppm @ 3:30

33° 26.60 N

112° 03.587 W

0.7 ppm @ 7:45

6:53 Sampled SG-45-10

0.6 ppm



TUES

6/15/04

UPPER Phoenix

NOTE: Reverse

7:01 begin drilling SG-46

7:10 Begin Purge SG-46-10

0" Vac PID 2.0 ppm 1:45 0.3 ppm

33° 26.8' 58" N

112° 03.5' 11" W

1.0 ppm @ 6:00

7:20 Sampled SG-46-10

PID 1.0 ppm

7:35 begin drilling SG-47

7:43 Begin Purge SG-47-10

0" vac 33° 26.603' N 0.12 ppm

112° 03.640' W

2.1 ppm @ 1:30

1.6 ppm @ 1:30

7:53 Sampled SG-47-10

1.0 ppm

TUES

6/15/04

UPPER Phoenix

8:18 begin drilling SG-48-10 N of tracks

John Hobbs 2 FIC, new good office

Rob Gonzalez

8:23 begin purging SG-48-10 0.2 ppm

0" vac 2.6 ppm @ 5:00

33° 26.617' N

112° 03.269' W

2.4 ppm @ 7:15

8:33 Sampled SG-48-10

2.0 ppm

8:50 begin drilling SG-49

8:56 begin purging SG-49-10

0" vac 5.3 ppm @ 2:15 0.00 ppm

33° 26.614' N

112° 03.284' W 2.1 ppm @ 7:00

9:06 Sampled SG-49-10

9:13 track FEB-2 # old being used

are changed during

data reporting. data checks completed in

46, 47, 48

UPPER

6/15/04 UPPER PHOTOGRAPH

9:28 begin drilling SG-50

9:32 begin purging SG-50-10

0" vac 2.6 ppm @ 11:15 0.0 Amb

33° 26.616N

112° 03.299W

2.311m @ 8:00

9:42 Sampled SG-50-10

2.6 ppm @

9:56 begin drilling SG-51

10:03 begin purging SG-51-10

0" vac 1.2 ppm @ 2:30 0.0 Amb

33° 26.617N

112° 03.298W

0.8 ppm @ 6:00

10:13 Sampled SG-51-10

0.9 ppm

10:24 begin drilling SG-52

UPPER

2000 E. Thruway UPPER MEANING 6/15/04

10:30 Begin purging SG-52-10

0" vac 0.3 ppm @ 1:00 0.19 Amb

33° 26.6177N

112° 03.273W

0.5 ppm @ 6:00

10:40 Sample SG-52-10

0.4 ppm

11:00 LUNEF

11:30 Discussion with Lab Large beach

check hit @ 51

was to 53

12:00 begin drill SG-53

12:09 begin purge SG-53-10

3.5" vac 1.6 ppm @ 2:30 0.2 Amb

33° 26.598N

112° 03.140W

0.7 ppm @ 8:00

12:18 Sample SG-53-10

0.7 ppm

FUES

6/15/04 UPRR Phoenix Lath E. Turner

12:27 begin drill SG-54  
mile widow in Juk Collar Bies  
12:37 Begin purge SG-54-10 0.2 ppm amb  
0" vac 12.5 c 2.10  
33° 26.596N  
112° 03.118W  
26.4 ppm @ 5:45  
12:47 Sampled SG-54-10 23.1 ppm  
12:49 Sampled SG-54-10-82600  
12:51 Sampled SG-54-10-70500  
13:05 begin drilling SG-55  
13:17 begin purge SG-55-10  
0" vac 36.2 ppm @ 0.3 ppm  
33° 26.602N  
112° 03.098W  
35.0 ppm @ 6:15  
13:27 Sampled SG-55-10  
39.2 ppm

FUES

6/15/04 UPRR Phoenix Lath E. Turner

13:50 begin drilling SG-51R  
located 2' E of SG-57  
13:57 begin purging SG-51R-10  
0" vac 5.7 ppm @ 4:00 0.2 ppm amb  
33° 26.625N  
112° 03.289W  
14:33 begin drilling SG-56  
14:40 begin purging SG-56-10  
0" vac 41.4 c 2:45 0.4 ppm amb  
33° 26.591N  
112° 03.092W  
47.2 ppm @ 7:30  
14:50 Sample SG-56-10  
51.6 ppm  
15:26 begin ~~drilling~~ SG-57  
15:32 begin purging SG-57 0.5 amb  
0.5" vac 33° 26.585N  
112° 03.104W  
14.4 ppm @ 13:15  
7.6 ppm @ 7:00

TUES

6/16/5/04 UBER Phoenix

15:42 Sampled SG-57-10

4.4 ppm

15:55 begin drilling SG-58

16:00 begin pump SG-58-10

0" vac 7.1 ppm CO<sub>2</sub> 0.4

3326.589 N

- 112.03.134 W 4.5 ppm 6:00

16:10 Sampled SG-58-10

4.4 ppm

16:40 Take 10-15 samples to

Aerotech

Judd G. Roney

Wed

Judd G. Roney - UBER Phoenix 6/16/5

5:00 arrive on site

5:15 Calibrate PID

5:45 Leak check - changed fitting

6:00 Start weekly

6:34 begin drilling SG-59 (weakened coils)

points under)

6:45 begin pump SG-59-10

0" vac 2.2 ppm @ 3:30 0.3 ppm and

33° 26.591 N

112.03.154 W

4.5 ppm @ 8:10

6:55 Sampled SG-59-10

1.1 ppm

7:04 begin drilling SG-60

7:25 begin pump SG-60-10

0" vac

33° 26.584 N

112.03.273 W

16.1 ppm @ 8:15



Wash

6/16/04 UPRR Phoenix

7:35 Sampled SG-60-10

16.7 ppm

7:45 began drilling SG-60-10

Concrete Drilling

8:34 began pugging SG-60-10 0.3 ppm

0" VAC 20.1 ppm

33° 26.584N

112° 03.292W

8:44 Sampled SG-60-10

16.1 ppm

8:52 began SG-62

Started with concrete core for  
to 2 feet to get through rock  
base

9:15 began pugging SG-62-10

0" VAC 5.9 ppm

33° 26.585N

112° 03.303W

6.3 ppm @ 8:45

Wash

Sept 8, 2004 UPRR Phoenix 6/16/04

9:25 Sampled SG-62-10

6.4 ppm

9:49 began SG-63 located 20

east of SG-56

10:02 began pugging SG-63 with

SG-49

33.9 ppm @ 1:29 1st 60

42.2 ppm @ 2:30 2nd 60

40.0 ppm @ 3:33 3rd 60

40.4 ppm @ 5:00 4th 60

10:07 Sampled SG-63-10

10:13 began drilling SG-64

20' N of SG-56

Det Det Ball-Fig

10:19 began pugging SG-64-10

11.0 ppm @ 1:00 1st 60

17.3 ppm @ 2:00 2nd 60

18.7 ppm @ 3:00 3rd 60

21.7 ppm @ 4:00 4th 60

21.7 ppm @ 4:00 4th 60

wed

6/16/64 V.P.R. Phoenix

10:24 Sampled SG-64-10

10:30 Sampled SG-64-10-~~85660~~

10:32 Sampled SG-64-10-T815D

10:48 Begin drilling SG-65

18' S of SG-56

10:58 Begin purge SG-65-10

0.2 amb

29.9 ppm @ 1:00 1 SG-65

73.1 ppm @ 2:00 2 SG-65

73.6 ppm @ 3:00 3 SG-65

74 ppm @ 4:00 4 SG-65

11:20 Begin Drilling SG-66

20' east of SG-65

11:38 Begin purge SG-66-10

0.2 ppm amb

122.0 ppm @ 1:00 1 SG-66

118.0 ppm @ 2:00 2 SG-66

112.0 ppm @ 3:00 3 SG-66

111.0 ppm @ 4:00 4 SG-66

wed

Lab E. Rovers V.P.R. Phoenix 6/16/64

11:34 Sampled SG-66-10

11:52 Sampled FEB-3

13:41 Begin drilling SG-67 (MOSW compound)

Mixer reduced @ 1.5

new hole 2' south of original

13:57 Begin purging SG-67-10

0" Vac 22.3 ppm @ 2:30 0.6 amb

33° 26.606W

112° 03.595W

36.5 ppm @ 6:45

14:07 Sampled SG-67-10

20.2 ppm

14:23 Begin drilling SG-68

14:29 Begin purging SG-68-10 0.8 ppm amb

0" Vac 12 SG-68-10

33° 26.597N

112° 03.606W

9.2 ppm @ 7:15

Wed

6/16/64 UPRR Phoenix Ladd & Hancock

14:39 Sampled SG-68-10

7.1 ppm

14:47 Begin drilling SG-69

14:54 begin Purgng SG-69-10

0" vac 5.3 ppm @ 2:00 0.6 ppm amb

33° 26.602N

112° 03.605W

2.6 ppm @ 7:30

15:04 Sampled SG-69-0

2.4 ppm @

15:16 begin drilling SG-70

15:23 begin Purgng SG-70

0" vac 2.6 ppm @ 2:30 0.4 Amb

33° 26.602N

112° 03.620W

2.6 ppm @ 8:00

15:33 Sampled SG-70-10

2.4 ppm

15:57 begin drilling SG-71

hit concrete @ 6" in 3 holes

mark to W side of section

fault

Wed

UPRR Phoenix 6/16/64

16:20 begin Purgng SG-71-10

0" vac 33° 26.630N 0.6 amb

112° 03.717W

2.1 ppm @ 2:00

1.6 ppm @ 7:00

16:30 sample SG-71-10

1.3 ppm

17:05 leave for Asbestos with  
70-15 sample

Ladd & Hancock

Thurs

UPRR Phoenix

6/17/04

5:20 Arrived on site

5:30 ~~EST~~ calibrated PID

6:00 Safety

6:13 begin drilling SG-72 in retention pond

6:15 begin purging SG-72-9

0" Vac 0.7 ppm @ 3:00 O.D. amb  
33° 26.293N  
112° 03.605W

0.3 ppm @ 7:15

6:25 Sampled SG-72-9  
0.5 ppm

6:33 begin drilling SG-73

6:43 begin purging SG-73-8-5  
0" Vac 0.4 ppm @ 1:45 O.D. amb

33° 26.295N

112° 03.606W

0.1 ppm @ 7:00

6:54.5 Sampled SG-73-8.5

0.0 ppm

Thurs

UPRR Phoenix

6/17/04

7:03 begin drilling SG-74-8.5  
wells of retention pond

7:10 Begin Purge SG-74-8.5 O.D. amb

0" Vac .5 ppm @ 1:30

33° 26.290N

112° 03.606W

7:20 Sampled SG-74-8.5

-1 ppm

8:00 began drilling SG-75

8:19 began purging SG-75-10

0" Vac 1.0 ppm @ 2:00 0.2 ppm amb

33° 26.323N

112° 03.529W

0.7 ppm @ 6:00

8:29 Sampled SG-75-10

0.4 ppm

Truly wash area

8:43 began drilling SG-76

retained Asphaltd 18" thick

used concrete cores



4 hrs

6/17/64 UPRR Phoenix Lord E. Howard

9:14 Begin Purge SG-76-10  
0" Vac 1.4 ppm @ 2:15 0.1 amb  
33° 26.39W  
112° 03.46W  
0.5 ppm @ 7:15

9:24 Sampled SG-76-10  
0.4 ppm

Mini Sumner 350 ml entrance  
2 min fill time

10:05 Begin Drilling SG-77-10

10:13 Begin Purge SG-77-10  
0" Vac 1.0 ppm @ 1:30 0.2 amb  
33° 26.427 N  
112° 03.469 W 0.3 ppm @ 1:00  
10:23 Sampled SG-77-10  
0.2 ppm

4 hrs

Lord E. Howard = UPRR Phoenix 6/17/64

10:48 Begin drilling SG-78 (Historical Important)  
10:54 Begin purging SG-78-10  
0" Vac 0.4 ppm @ 2:05 0.2 amb  
33° 26.475 N  
112° 03.376 W  
0.3 ppm @ 6:40

11:04 Sampled SG-78-10 0.1 ppm  
11:05 Sampled SG-78-10-82600  
11:07 Sampled SG-78-10-101510

11:20 Begin drilling SG-79

11:32 Begin purging SG-79-9.5  
0" Vac 0.2 ppm @ 1:00 0.0 amb  
33° 26.501 N  
112° 03.379 W

11:42 Sampled SG-79-9.5  
0.1 ppm @ 8:00

Thursday

6/17/04 UPRR Phoenix David E. Menden

12:01 Begin Drilling SG-80

Background Sample

12:05 FEB-4 Collection

~~12:10~~ Begin Drilling

12:16 Begin Purge SG-80-10

0" VAC .8 ppm e 1:30 .2 ppm amb

330 26.534 N

112° 03.832 W

0.7 ppm

12:25 Sampled SG-80-10 0.6 ppm

12:26 Sampled SG-80-10-8260P

12:28 Sampled SG-80-10-7015D

12:57 Changed tubing to 17' Begin Drilling SG-81

Auger resumed @ 12.5' of cobbles

thurs

13:12 David E. Menden UPRR Phoenix 6/17/04

13:12 Begin Purge SG-81-12.5

0" VAC 0.7 ppm e 1:20 0.2 amb

33° 26.520 W

112° 03.621 W

0.2 ppm e 7:00

13:22 Sampled SG-81-12.5

0.4 ppm

14:56 Begin Drilling SG-82

46' s 4 SG-65

15:06 Begin Purge SG-82-9

0.6 ppm

43.6 ppm 01:00 12:00

63.9 ppm 02:00 24:00

51.4 ppm e 3:00 54:00

59.5 ppm e 4:20 94:00

15:11 Sampled SG-82-9

33° 26.577 N 112° 03.094 W

15:18 Sampled SG-82-9-7015D

Flow controller fitting knocked loose  
lost all the way down

Thurs

6/17/64

UPAC Phoenix

John E. Brown

15:36 Began drilling SG-83

40' west of SG-82

33° 26' 57.7N 112° 03' 10.1W

15:47 begin purge SG-83

40.8 ppm @ 1:00 1<sup>st</sup> 0.6 ppm

66.1 ppm @ 1:42 2<sup>nd</sup> 60

60.7 ppm @ 2:25 3<sup>rd</sup> 60

60.9 ppm @ 3:40 4<sup>th</sup> 60

15:57 Sampled SG-83-10

16:09 began drilling SG-84

40' east of SG-82

33° 26.576N 112° 03.091W

16:25 begin purge SG-84-10 0.3 ppm

90.4 ppm 1:00 1<sup>st</sup> 60

65.4 ppm 1:44 2<sup>nd</sup> 60

68.0 ppm 2:15 3<sup>rd</sup> 60

67.0 ppm 3:00 4<sup>th</sup> 60

16:28 Sampled SG-84-10

Thurs

UPAC Phoenix 6/17/64

17:05 Take 70-15 Samples to

hero tech

17:50 Return to site. Scott

and I move around site

with drill rig and asphalt

patch repairing drill holes

in asphalt.

19:05 Leave site

≈ 3 gallons of wash water

left on south side of

yard office near loading

back for evaporation.

John E. Brown

Tues

10/24/04 UPRR Phoenix AZ & S. Zone

5:15 Arrive on site  
 5:50 LAB ARRIVES  
 6:50 Drill Rig arrives  
 had flat tire  
 6:55 Rich (underground locator) arrives  
 7:30 H & S meeting  
 Take Rich around to avoid street  
 while Scott sets up  
 8:15 Rich finished  
 8:27 3rd attempt SG-85  
 had substance @ 1'  
 8:30 4th attempt @ SG-85  
 drilled concrete abandoned  
 8:53 5th attempt @ SG-85  
 53' sd spur  
 9:10L Begin puzing SG-85 -110  
 33° 26' 56" 2N 112° 03' 07" W 0.0 and  
 1st @ 30 0.0 ppm  
 2nd @ 1:15 0.6 ppm  
 3rd @ 2:00 0.0 ppm  
 4th @ 2:50 0.1 ppm  
 9:36 Sampled SG-85-10

Tues

10/24/04 UPRR Phoenix AZ & S. Zone

10:04 Begin drilling SG-86 80' v off SG-83  
 10:15 Begin drilling SG-86 again 2' to  
 the end - rocks  
 10:27 Begin puzing SG-86-10  
 33° 26' 58" N  
 112° 03' 12" W  
 1st @ 0.0 ppm @ 1'00  
 2nd @ 0.0 12.1 ppm @ 2'00  
 3rd @ 0.0 12.1 ppm @ 3'00  
 4th @ 0.0 16.5 ppm @ 4'00  
 10:32 Sampled SG-86-10  
 11:03 Begin drilling SG-87  
 105' E of SG-84  
 18' south of track  
 19' N of Spar track  
 12  
 11:15 Begin puzing SG-87-9  
 46 ppm @ 1'00 14.6  
 33° 26' 58" N 1.5 ppm @ 2'00 24.6  
 112° 03' 07" W 0.0 ppm @ 3'15 3.6  
 0.9 ppm @ 4'00 4.6



Thurs

6/28/64

UPLD Phoenix  
Sampled SG-87-7

11:37  
began drilling SG-88  
59' from SG-84  
55' from SG-87  
6' N of Spur track

11:58 began pouring SG-88-10

6:10<sup>3</sup> ppm @ 100 1<sup>st</sup> 60  
80.8 ppm @ 150 2<sup>nd</sup> 60  
87.0 ppm @ 230 3<sup>rd</sup> 60  
85.1 ppm @ 3130 4<sup>th</sup> 60

33° 26.583N

112° 03.068W

12:01 Sampled SG-88-10

12:14 began drilling SG-89  
82' w of ~~88~~ SG-88  
46' from SG-84  
6' N of Spur track

Thurs

6/29/64

UPLD Phoenix

12:31 began pouring SG-89-8.5  
33° 26.583N 112° 03.094W  
56.7 ppm @ 100 1<sup>st</sup> 60  
60.6 ppm @ 150 2<sup>nd</sup> 60  
59.6 ppm @ 230 3<sup>rd</sup> 60  
59.8 ppm @ 3130 4<sup>th</sup> 60

12:34 Sampled SG-89-8.5

12:35 Sampled SG-89-8.5-8260D

12:37 Sampled SG-89-8.5-7815D

13:03 began drilling SG-90-

6' N of spur 130' W of SG-89

13:12 began pouring SG-90-10

33° 26.586N 112° 03.120W 19.7 ppm @ 50 1<sup>st</sup> 60  
22.8 ppm @ 130 2<sup>nd</sup> 60  
23.6 ppm @ 215 3<sup>rd</sup> 60  
22.1 ppm @ 3130 4<sup>th</sup> 60

13:16 Sampled SG-90-10

13:36 began drilling SG-91  
6' N of Spur 135' West of SG-90

Tues

6/29/64 UPR Phoenix John E. Hanner

13:47 Sampled FEB-5

14:22

~~13:47~~ began Boring SG-91-10

33° 26.55' N 0.7 ppm @ 150 1' 0.0 mbs

112° 03.14' W 2.4 ppm @ 1:30 2

3.6 ppm @ 2:45 3

1.8 ppm @ 3:30 4

USMC M.V. can because of problems with lab

14:26 Sampled SG-91-10

John E. Hanner

Wed

John E. Hanner UPR Phoenix 6/29/64

4:30 Arrive on site

5:30 Safety briefing

5:57 began SG-92-10

at 80' S of spur track

SG-95 to SG-92 = 158'

used drill to break up top 18"

6:24 began pugging SG-92-18

33° 26.55' N 3.9 ppm @ 1:00 15' 0.0 mbs

112° 03.09' W 4.9 ppm @ 2:00 2 14' 40

3.3 ppm @ 2:40 3 14' 60

2.3 ppm @ 3:30 4 14' 60

6:29 Sampled SG-92-10

6:43 began drilling SG-93

72' South of SPUR

35' east of SG-87

41' W of tracks

drill to 18"

7:08

Purged SG-93-10

33° 26.57' N

112° 03.05' W



Wed

6/20/64

VPR Phoenix

Dred E. Mar

SG-93-10

0.0 and

Purging

0.0 ppm @ 1:45 1<sup>st</sup> 600.0 ppm @ 1:15 2<sup>nd</sup> 600.0 ppm @ 2:45 3<sup>rd</sup> 600.0 ppm @ 3:20 4<sup>th</sup> 60

7:13 Sample SG-93-10

8:20 Begin drilling SG-94

G4 is E-1C track locked out

3" of track

102' to SG-85

82' to SG-92

8:21 Purging SG-94

0.0 ppm @ 2:50 1<sup>st</sup> 60 0.0 and3<sup>rd</sup> 26.5480.6 ppm @ 1:30 2<sup>nd</sup> 60112° 03.082W 0.0 ppm @ 2:40 3<sup>rd</sup> 601.3 ppm @ 3:20 4<sup>th</sup> 60

8:25 Sampled SG-94-10

8:26 Sampled SG-94-10-82600

8:28 Sampled SG-94-10-70152

Wed

Dred E. Mar VPR Phoenix 6/20/64

8:50 begin drilling SG-95

8:58 Purging SG-95-10

1.8 ppm @ 2:50 1<sup>st</sup> 60 0.0 and33° 26.532N 1.6 ppm @ 1:20 2<sup>nd</sup> 60112° 03.114W 0.3 ppm @ 2:10 3<sup>rd</sup> 601.5 ppm @ 3:05 4<sup>th</sup> 60

8:102 Sampled SG-95-10

9:25 drilling SG-96

11' stuck track

87' sample SG-56

5' stuck track at spur

9:33 Purging SG-96-10

33° 26.594N 2.7 ppm @ 1:00 1<sup>st</sup> 60 0.0 and112° 03.082W 39.7 ppm @ 2:00 2<sup>nd</sup> 602.4 ppm @ 2:50 3<sup>rd</sup> 601.4 ppm @ 3:50 4<sup>th</sup> 60

9:37 Sampled SG-96-10

Wed

6/29/64

VIRAC Phoenix

Zobell E. Inman

10:05 Begin drilling SG-97

97' W of SG-92 used hand drill

67' S of SPT

63' N of track

10:17 Paving SG-97

33° 26.537N

0800pm @ 50

00 ankle

112° 05.419W

0800pm @ 1:50

760pm @ 2:50

510pm @ 3:48

10:25 Sampled SG-97 @ 10

begin

10:42 Begin drilling SG-98

used hand drill

75' Soil bacteria

Concrete @ 6" to 18"

4" Dark stained Sinterite

Clite asphalt

Wed

Zobell E. Inman

VIRAC Phoenix

6/29/64

11:25 Begin Pave SG-98-10

33° 26.563N 2:20pm @ 1:00 00 ankle

112° 03.248W 5:00pm @ 2:00

5:00pm @ 3:00

4:00pm @ 3:50

11:29 Sampled SG-98-10

11:50 Begin drilling SG-99

Concrete 15' east of good station

2' 2" thick concrete

dependent out of ground

12:30 Lunch

13:17 Begin SG-99 again

Just N of pavement hit horse

rock @ 1 ft. moved

2' west hit rock @ 2'

moved 3' west

105' @ 5' 25' N of 5' -

13:36 Begin paving SG-99

33° 26.587N 0:00pm @ 45' 1st 60 00 ankle

143° 03.750W 3:11pm @ 1:35 2nd 60

2:20pm @ 2:40 3rd 60

2:40pm @ 3:40 4th 60

Wed

8/29/04 UPR Phoenix Vol E Hm

13:40 Sampled SG-99-10

14:15 Begin Drilling SG-100

100' west of SG-97

72' S of spur

34' N of track

14:37 Purging SG-100-10

33° 26.539 N 1:7 ppm @ 1:00 0.0 and

112° 03.138 W 44 ppm 1:50

3:6 ppm 3:00

3:1 ppm 3:50

14:51 Sampled SG-100-10

15:25 Begin Drilling SG-101

135' W of SG-100

67' S of spur

30' N of track

15:48 Begin Purge SG-101-9.0

33° 26.532 N

112° 03.159 W

Wed

Vol E Hm UPR Phoenix 8/29/04

15:49 3.5 ppm @ 1:50

1:7 ppm @ 1:30 0.0 and

4:1 ppm @ 2:30

1:5 ppm @ 3:00

15:52 Sampled SG-101-9.0

16:08 Begin SG-102

(in case SG-101 not P.D.)

broke spud tip, get good

drill

16:50 Redrill SG-102

52' N of track 117' from SG-101

16:15 Purge SG-102-7 33° 26.531 N

143' from SG-1 38 ppm @ 1:50 112° 03.187 W

5:1 ppm @ 1:30 0.0 and

17:15 Sample 3.4 ppm @ 2:30

3.1 ppm @ 3:00

17:19 Sample SG-102-7.0

Mini-Sam

6/29/09

Wed  
VRAO Phoenix

17:35 Begin drilling SG-103

Pre drilled with hand drill

120' Eof SG-102

5' N of track

38° 26.526N

112° 03.212W

17:43 Begin pouring SG-103-8

3.0	ppm @ 1:00	15:60	0.0 amb
3.5	ppm @ 1:50	22:60	
3.0	ppm @ 3:00	34:60	
3.1	ppm @ 3:50	45:60	

17:48 Sampled SG-103-8

40.00 E. Phoenix

**APPENDIX E**  
**LABORATORY REPORTS AND CHROMATOGRAMS**